

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

RECEIVED

(Do not write above this line)

State Well No. 4511e-23da

State Permit No.

SEP 12 1979

(1) OWNER:

Name David J. Koch WATER RESOURCES DEPT
Address 740 N. E. 29th P. SALEM, OREGON
Canby, Oregon 97013

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
☐ Jetted ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☒ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

8" Diam. from #1 238 ft. to 250 ft. Gage
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Mills knife
Size of perforations 3/8 in. by 2 1/2 in.
48 perforations from 119 ft. to 127 ft. 141 ft.
48 perforations from 133 ft. to 146 ft. 186 ft.
480 perforations from 146 ft. to ft. ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " " " "
Air 250 " total " 5 "
Peller test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement
Well sealed from land surface to 20 ft.
Diameter of well bore to bottom of seal 12 in.
Diameter of well bore below seal 8 in.
Number of sacks of cement used in well seal 27 sacks
How was cement grout placed?
Pressure grout

Was a drive shoe used? ☒ Yes ☐ No Plug Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number
NE 1/4 SE 1/4 Section 23 T. 48 R. 1E W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 93 ft.
Static level 40 ft. below land surface. Date 8/17/79
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 8
Depth drilled 260 ft. Depth of completed well 260 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top soil	0	1	
Clay, brown	1	22	
Clay, blue, sandy	22	39	
Gravel med.	39	58	
Gravel med. sand	58	67	
Gravel, clay, blue	67	76	
Sandstone, med. green	76	87	
Claystone, blue	87	93	
Sandstone, green	93	102	WB
Gravel, med.	102	109	
Sandstone, green	109	115	
Clay, grey	115	119	
Sandstone, green	119	127	WB
Claystone, brown	127	133	
Sandstone, brown	133	141	WB
Clay, brown	141	146	
Sandstone, green, grey	146	186	WB
Claystone, blue, green	186	194	
Sand, brown	194	201	
Clay, grey	201	260	

Work started 8/14 19 79 Completed 8/18 19 79

Date well drilling machine moved off of well 8/18 19 79

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Byron B. Stadel Date 8/28, 19 79
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1371

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name C. G. Westerberg
(Person, firm or corporation) (Type or print)

Address Rt. 1, Box 151, Mulino, Oregon

[Signed] C. G. Westerberg
(Water Well Contractor)

Contractor's License No. 86 Date 8/28, 19 79