

JUL 11 1980

WATER WELL REPORT

CLAC
12530

WATER RESOURCES DEPARTMENT
SALEM, OREGON 97310
within 30 days from the date
of well completion.

STATE OF OREGON
SALEM, OREGON (Please type or print)

State Well No. 45/IF-26 da

State Permit No.

(Do not write above this line)

(1) OWNER:

Name Richard Gingerich
Address 10765 S. Barnards Rd.
Canby, Oregon 97013

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Drilled ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

10 " Diam. from 0 ft. to 198 ft. Gage 250
190 " Diam. from 190 ft. to 260 ft. Gage 250
" Diam. from " ft. to " ft. Gage "

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used torch
Size of perforations 10 in. by 1/4 in.
200 perforations from 208 ft. to 260 ft.
perforations from " ft. to " ft.
perforations from " ft. to " ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from " ft. to " ft.
Diam. Slot size Set from " ft. to " ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Aqua Pump

a pump test made ☒ Yes ☐ No If yes, by whom?
Yield: 125 gal./min. with 77 ft. drawdown after 4 hrs.
150 " 99 " 7 "
175 " 121 " 8 "
er test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used cement
Well sealed from land surface to 18 ft.
Diameter of well bore to bottom of seal 14 in.
Diameter of well bore below seal 10 in.
Number of sacks of cement used in well seal 16 sacks
How was cement grout placed?
pressure grouted
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from " ft. to " ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number D206-80
NE 1/4 SE 1/4 Section 26 T. 4S R. 1E W.M.

Bearing and distance from section or subdivision corner
Heinz Rd.

(11) WATER LEVEL: Completed well.

Depth at which water was first found 105 ft.
Static level 33 ft. below land surface. Date 6/12/80
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 10

Depth drilled 260 ft. Depth of completed well 260 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
topsoil	0	2	
clay brown	2	33	
gravel cemented	33	105	
gravel water bearing	105	110	
gravel cemented	110	125	
gravel water bearing	125	130	
gravel cemented	130	173	
sandstone black w/bearing	173	176	
sand brown	176	195	
clay	195	208	
gravel & sand w/bearing	208	224	
clay gray	224	236	
gravel & sand	236	241	
clay blue	241	247	
sandstone black w/bear	247	260	

Work started 6/4/80 19 Completed 6/12/80 19
Date well drilling machine moved off of well 6/12/80 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Brian Blocker Date 6/12/80, 19.
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1169

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name S & M Drilling Inc.
(Person, firm or corporation) (Type or print)

Address 399 S E Walnut Canby, Ore 97013

[Signed] [Signature] (Water Well Contractor)

Contractor's License No. 497 Date 6/12/80, 19.