

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

CLAC
12531

APR 6 1989

48/C/24 ad

WATER RESOURCES DEPT. (START CARD) # 9964

(1) OWNER: Well Number: _____
Name Bruce Hoskins-ToKar's Nursery
Address 38191 SE Hudson Rd.
City Boring State OR Zip 97009

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other _____

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes No
Explosives used ☐ ☒ Type _____ Amount _____
Depth of Completed Well 251 ft.

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
12"	0	20	Cement	0	20	35 sacks
8"	20	251	—	—	—	—

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other _____ Pressure grout

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8"	+2	250	250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Holte air perf.
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
164	168	1/2 x 1 1/2	144			☒	☐
188	193	"	200			☒	☐
200	212	"	480			☒	☐
217	222	"	208			☒	☐
232	248	"	609			☒	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing
Artesian

Yield gal/min	Drawdown	Drill stem at	Time
300		250	1 hr.

Temperature of water _____ Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Clack. Latitude _____ Longitude _____
Township 4S N or S, Range 1E E or W, WM.
Section 26 SE 1/4 NE 1/4
Tax Lot _____ Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) Intersection of
Heinz & Elisha Rd.

(10) STATIC WATER LEVEL:

27.5 ft. below land surface. Date 3-31-89
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 32'

From	To	Estimated Flow Rate	SWL
64	83	10	27.5
94	106	50	27.5
164	244	300	27.5

(12) WELL LOG:

Ground elevation _____

Material	From	To	SWL
Soil	0	1	
Clay brn med	1	11	
Clay grey med	11	23	
Clay grey with gravel interbeds	23	32	
Gravel med brn	32	64	
Sand & gravel large brn med	64	83	27.5
Clay brn with gravels	83	88	
Gravel cemented	88	94	
Sand & gravel med brn	94	106	27.5
Gravel & clay	106	111	
Sand & gravel	111	114	
Clay blue	114	118	
Gravel dry	118	124	
Clay grey	124	164	27.5
Sand coarse grey	164	168	27.5
Clay grey	168	188	"
Clay grey Sand & gravel grey	188	193	"
Clay blue	193	206	"
Sand & gravel grey med	206	212	"
Gravel packed	212	217	"
Sand coarse small gravel	217	222	"
Clay grey	222	232	"

CONTINUED ON ADDITIONAL PAGE

Date started 3-27-89 Completed 3-30-89

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed Byron B. Stedette WWC Number 1358
Date 4-4-89

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed [Signature] WWC Number 723
Date 4-5-89