

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT RECEIVED

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. _____

State Permit No. 451E-269a

AUG 18 1976
WATER RESOURCES DEPT.

(1) OWNER:

Name Chas. R. Morgan
Address 28185 S. Elisha Rd.
Canby, Oregon, 97013

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
10" Diam. from 0 ft. to 160 ft. Gage 250.
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used Mills Knife

Size of perforations 1 1/2 in. by 2 1/2 in.
256 perforations from 139 ft. to 155 ft.
336 perforations from 104 ft. to 132 ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____

Type _____ Model No. _____

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: 220 gal./min. with 135 ft. drawdown after 1 1/2 hrs.

" " " "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement

Well sealed from land surface to 18 ft.

Diameter of well bore to bottom of seal 15 in.

Diameter of well bore below seal 10 in.

Number of sacks of cement used in well seal 7 sacks

Number of sacks of bentonite used in well seal sacks

Brand name of bentonite

Number of pounds of bentonite per 100 gallons
of water lbs./100 gals.

Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number

NE 1/4 NE 1/4 Section 26 T. 4S R. 1E W.M.

Bearing and distance from section or subdivision corner

Mt. View Acres

(11) WATER LEVEL: Completed well.

Depth at which water was first found 28 ft.

Static level 15 ft. below land surface. Date 8-14-76

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 10

Depth drilled 220 ft. Depth of completed well 220 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top soil	0	5	
Brown Clay	5	22	
Sandy, gray, clay	22	45	
Cemented gravel	45	92	
Gravel water	92	98	
Brown clay	98	104	
Gravel, water	104	132	15
Blue clay	132	139	
Gavel, water	139	143	15
Gravel, brown sand, water	143	150	15
Brown, sand, water	150	155	15
Brown clay	155	165	
Blue, clay, stone	165	185	
Sandstone, soft	185	200	
Blue clay, stone	200	215	
Blue clay, sticky	215	220	

Work started 8-13 19 76 Completed 8-14 19 76

Date well drilling machine moved off of well 8-14 19 76

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] David Donnelly Date 8-16, 19 76
(Drilling Machine Operator)

Drilling Machine Operator's License No. 883

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name S & M Drilling & Supply, Inc.
(Person, firm or corporation) (Type or print)

Address 399 S.E. Walnut St., Canby, Or., 97018

[Signed] Walter Mose
(Water Well Contractor)

Contractor's License No. 497 Date 8-16, 19 76

(USE ADDITIONAL SHEETS IF NECESSARY)