

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date of well completion.

CLAC
12539

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

RECEIVED
AUG 13 1973

State Well No.

STATE ENGINEER

SALEM, OREGON

State Permit No.

45/E-26⁶

(1) OWNER:

Name Dan Payzant
Address Rt. 2, Box 304
Canby, Oregon 97013

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dig ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

10" Diam. from 0 ft. to 226 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Mills knife

Size of perforations 1/2 in. by 3 in.
36 perforations from 67 ft. to 71 ft.
66 perforations from 87 ft. to 94 ft.
90 perforations from 134 ft. to 154 ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

gal./min. with ft. drawdown after hrs.
" " " " "
" " " " "
Bailer test 54 gal./min. with 6 ft. drawdown after 2 hrs.

Artesian flow 55 g.p.m.
Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Bentonite
Well sealed from land surface to 28 ft.
Diameter of well bore to bottom of seal 14 in.
Diameter of well bore below seal 10 in.
Number of sacks of cement used in well seal 3 sacks
Number of sacks of bentonite used in well seal 3 sacks
Brand name of bentonite National
Number of pounds of bentonite per 100 gallons of water 100 lbs./100 gals.
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number
NW 1/4 Section 26 T. 4S R. 1E W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 67 ft.
Static level 31 ft. below land surface. Date 7/17/73
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 10

Depth drilled 242 ft. Depth of completed well 242 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil, brown	0	2	
Clay, tan, hard	2	8	
Clay, silty, tan	8	22	
Clay, blue	22	26	
Clay, tan	26	36	
Gravel & clay	36	39	
Clay, tan	39	44	
Gravel, med.	44	67	
Gravel, loose, med.	67	71	31
Clay, tan	71	73	
Gravel & clay	73	76	
Gravel, med.	76	78	
Clay, tan some gravel	78	84	
Galv, brown	84	87	
Gravel & sand, brown, med.	87	94	31
Gravel & clay, tan	94	103	
Clay, grey, sticky	103	134	
Gravel, med.	134	136	29
Continued			

Work started 7/14 1973 Completed 8/1 1973
Date well drilling machine moved off of well 8/1 1973

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] C. G. Westerberg Date 8/8, 1973
(Drilling Machine Operator) 86

Drilling Machine Operator's License No.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name C. G. Westerberg (Type or print)
(Person, firm or corporation)

Address Rt. 1, Box 151, Mulino, Oregon

[Signed] C. G. Westerberg (Water Well Contractor)
Contractor's License No. 86 Date 8/8, 1973

