

WATER WELL REPORT

STATE OF OREGON

RECEIVED

JUL 2 1 1982

State Well No.

State Permit No.

WATER RESOURCES DEPT.
SALEM, OREGON

(1) OWNER:

Name Tim Wong
 Address 28875 S. Dryland Rd.
 City Canby State Or.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐ Domestic ☐ Industrial ☐ Municipal ☐
 Rotary Mud ☐ Dug ☐ Irrigation ☒ Test Well ☐ Other ☐
 Cased ☐ Bored ☐ Thermal: ☐ Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
 Threaded ☐ Welded ☒
 6" Diam. from 0 ft. to 165 ft. Gauge .250
 " Diam. from ft. to ft. Gauge

(6) LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used Air perforator
 Size of perforations in. by in.

7.2" perforations from 7.9 ft. to 8.4 ft.
 7.2" perforations from 9.3 ft. to 9.7 ft.
 7.2" perforations from 13.0 ft. to 13.4 ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
 Type Model No.
 Diam. Slot Size Set from ft. to ft.
 Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

When pump test made? ☒ Yes ☐ No If yes, by whom? Driller
 Yield: 60 gal./min. with 22 ft. drawdown after 1 hrs.

Air test gal./min. with drill stem at ft. hrs.
 Bailer test gal./min. with ft. drawdown after hrs.
 Artesian flow g.p.m.
 Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Cement
 Well sealed from land surface to 19 ft.
 Diameter of well bore to bottom of seal 1.0 in.
 Diameter of well bore below seal 6 in.
 Number of sacks of cement used in well seal 13 sacks
 How was cement grout placed? Pressure grouted from 19 ft. to land surface.

Was pump installed? Yes Type Sub HP 5 Depth 126 ft.
 Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
 Did any strata contain unusable water? ☐ Yes ☒ No
 Type of Water? depth of strata
 Method of sealing strata off
 Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.
 Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number 212
 SW 1/4 SW 1/4 Section 26 T. 4S R. 1E W.M.
 Tax Lot # Lot Blk Subdivision
 Address at well location: 28875 S. Dryland Rd.
Canby, Or. 97013

(11) WATER LEVEL: Completed well.

Depth at which water was first found 38 ft.
 Static level 19 ft. below land surface. Date 6/28/82
 Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 165 ft. Depth of completed well 165 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top soil	0	2	
Clay, brown	2	21	
Clay, sand, blue, black, fn.	21	26	
Gravel, compacted	26	29	
Clay, blue	29	38	
*Gravel, compacted	38	84	
Clay, sand, brown, fine	84	88	
*Gravel, compacted	88	93	
Clay, brown	93	97	
Clay, blue	97	130	
*Gravel, compacted	130	134	
Clay, blue	134	158	
*Gravel, compacted	158	160	
Clay, blue	160	165	

Work started 6/22 19 82 Completed 6/28 19 82
 Date well drilling machine moved off of well 6/28 19 82

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Bob Kern Date 7/1/82, 19.82
 (Drilling Machine Operator)

Drilling Machine Operator's License No. 994

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name B. & G. Drilling (Type or print)
 (Person, firm or corporation)

Address 10030 S. Macksburg Rd. Canby, Or.

[Signed] George Wainwright
 (Water Well Contractor)

Contractor's License No. 637 Date 7/1/82, 19.82

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,

SALEM, OREGON 97310

within 30 days from the date of well completion.

SP*12658-690