

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

RECEIVED

MAY 20 1986

PLEASE TYPE or PRINT IN INK

WATER RESOURCES DEPT.

SALEM, OREGON

CLAC
012773

43/1E-34abc

(for official use only)

(1) OWNER:

Name STEVE GERMANY

Address JACKSON RD

City CANEY

State Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☐ Cable ☒ Driven ☐ Rig ☐

Rotary Mud ☐ Dug ☐

Cable ☒ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Irrigation ☐ Industrial ☐ Municipal ☐

Thermal: ☒ Withdrawal ☐ ReInjection ☐

Other: ☐ Piezometric ☐ Grounding ☐ Test ☐

(5) CASING INSTALLED:

Steel ☒ Welded ☒ Plastic ☐

Threaded ☐ Welded ☒

....." Diam. from ft. to ft. Gauge 25

....." Diam. from ft. to ft. Gauge

LINER INSTALLED:

Steel ☐ Plastic ☐

Threaded ☐ Welded ☐

....." Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

STAR Perforated? ☐ Yes ☐ No

Size of perforations 1.5 in. by 3/8 in.

..... perforations from 91 ft. to 185 ft.

..... perforations from 205 ft. to 224 ft.

..... perforations from 255 ft. to 279 ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot Size Set from ft. to ft.

Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Well: 300 gal./min. with 240 ft. drawdown after 5 hrs.

Air test 300 gal./min. with AR LINE at 275 ft. 5 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Granular Bentonite

Well sealed from land surface to ft.

Diameter of well bore to bottom of seal in.

Diameter of well bore below seal in.

Amount of sealing material sacks ☒ pounds ☐

How was cement grout placed? Granular Bentonite Method

.....

.....

.....

.....

.....

.....

.....

.....

.....

.....

.....

.....

.....

.....

(10) LOCATION OF WELL by legal description:

County CLACKAMAS SW $\frac{1}{4}$ NE $\frac{1}{4}$ of Section 34 of

Township 4S Range 1E (Range is East or West) WM.

(Township is North or South)

Tax Lot Lot Block Subdivision

MAILING ADDRESS OF WELL (or nearest address)

.....

.....

(11) WATER LEVEL of COMPLETED WELL:

Depth at which water was first found 25 ft.

Static level 35 ft. below land surface. Date May 06, 1986

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing in.

Depth drilled 285 ft. Depth of completed well 285 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOPSOIL	1	3	
CLAY BN	3	23	
CLAY GREY	23	26	
CEMENT GRAVEL	26	85	
CLAY TAN	85	91	
CEMENT GRAVEL	91	100	
CLAY TAN	100	116	
CEMENT GRAVEL	116	136	
CLAY GREY	136	157	
CEMENT GRAVEL	157	163	
CLAY GREY	163	174	
CEMENT GRAVEL	174	185	
CLAY BLUE	185	210	
SAND CLAY LAYERS	210	224	
SILT BLACK	224	235	
CLAY BLUE	235	255	
SAND LAYERS IN GREEN CLAY	255	265	
SAND LAYERS GREY CLAY	265	281	
CLAY	281	285	

note: Depth measured from top of well (ie. 1' above ground level)

Date work started Apr 07 86 /completed May 06 86

Date well drilling machine moved off of well May 07 19 86

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Date, 19

(bonded) Water Well Constructor Certification:

Bond \$834200 Issued by: Thomas Haun

(number)

(Surety Company Name)

On behalf of BECK WELL DRILLING

(type or print name of Water Well Constructor)

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

(Signed) Richard Beck

(Water Well Constructor)

(Dated) May 7, 1986

NOTICE TO WATER WELL CONSTRUCTOR

The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,

SALEM, OREGON 97310

within 30 days from the date of well completion.

SP*46866-690



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.oregon.gov/owid

Application for Well ID Number

Do not complete if the well already has a Well Identification Number.

RECEIVED

DEC 18 2024

I. OWNER INFORMATION

OWRD

Current Owner Name (please print): Wayne and Amanda Stehely

Mailing Address: 29490 S. Jackson Rd

City, State, Zip: Canby, OR 97013

Mail Well ID to: ☒ SAME AS ABOVE ☐ In Care Of (C/O)

Name & Address: _____

City, State, Zip: _____

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 4S (North / South) Range: 1E (East / West) Section: 34 NW 1/4 of the SE 1/4

Tax Lot (usually last 3-5 numbers of Tax Map #): 1100 County Clackamas

GPS Coordinates: 45.176373, -122.667635 per WR permit G-18235 map

Street Address of Well, City: No site address nearest is 29490 S. Jackson RD, Canby

If the property had a different street address in the past: _____

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Report, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Irrigation

Date Well Constructed (or property built): May 6, 1986 Total Well Depth: 285 ft Casing Diameter: 8 inch

Owner at time the well was constructed (if known): Steve Germany Well Report # (if known): CLAC 12773

Other Information: _____

SUBMITTED BY (please print): Amanda Staehely

PHONE: (503) 320-3466 EMAIL &/or FAX: Amanda@columbia-nursery.com

To send the completed application, you may MAIL it to: Oregon Water Resources Dept. 725 Summer St NE, Suite A, Salem, Oregon 97301
Or EMAIL the completed PDF form to: Ladeena.K.Ashley@water.oregon.gov, or FAX it to: (503) 986-0902.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

12-18-2024

Well Report Number:

CLAC 12773

Well Identification #:

L-157010