

NOTICE TO WATER WELL CONTRACTOR  
The original and first copy of this report  
are to be filed with the

CLAC 12922  
WATER WELL REPORT  
STATE OF OREGON  
(Please type or print)  
(Do not write above this line)

CLAC  
012922  
State Well No. 431/E-5ca  
State Permit No.

WATER RESOURCES DEPARTMENT,  
SALEM, OREGON 97310  
within 30 days from the date  
of well completion.

RECEIVED

JAN 30 1979

WATER RESOURCES DEPT.

(1) OWNER: SALEM, OREGON

Name A. J. Millar  
Address P.O. Box 23  
Conby, Ore. 97013

(2) TYPE OF WORK (check):

New Well  Deepening  Reconditioning  Abandon   
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL: (4) PROPOSED USE (check):

Rotary  Driven  Domestic  Industrial  Municipal   
Cable  Jetted  Irrigation  Test Well  Other   
Dug  Bored

CASING INSTALLED: Threaded  Welded   
6" Diam. from 0 ft. to 80 ft. Gage 250  
5 9/16" Diam. from 67 ft. to 87 ft. Gage 188

PERFORATIONS: Perforated?  Yes  No.

Size of perforator used Torch  
Size of perforations 1/8 in. by 8 in.  
32 perforations from 67 ft. to 87 ft.

(7) SCREENS: Well screen installed?  Yes  No

Manufacturer's Name  
Type Model No.  
Diam. Slot size Set from ft. to ft.  
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS: Drawdown is amount water level is lowered below static level

Was a pump test made?  Yes  No If yes, by whom? driller  
Yield: 25 gal./min. with 19 ft. drawdown after 1 1/2 hrs.  
Bailer test gal./min. with ft. drawdown after hrs.  
Artesian flow g.p.m.  
Temperature of water 54 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement  
Well sealed from land surface to 19 ft.  
Diameter of well bore to bottom of seal 10 in.  
Diameter of well bore below seal 6 in.  
Number of sacks of cement used in well seal sacks  
How was cement grout placed? Cement was pressure grouted from 19 ft. to surface  
Was a drive shoe used?  Yes  No Plugs Size: location ft.  
Did any strata contain unusable water?  Yes  No  
Type of water? depth of strata  
Method of sealing strata off  
Was well gravel packed?  Yes  No Size of gravel:  
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number 96  
NE 1/4 SW 1/4 Section 5 T. 4S R. 7E W.M.  
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 40 ft.  
Static level 31 ft. below land surface. Date 1-25-79  
Artesian pressure lbs. per square inch. Date

(12) WELL LOG: Diameter of well below casing 6"

Depth drilled 87 ft. Depth of completed well 87 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top soil	0	2	
Clay, brown	2	7	
Clay, gravel	7	12	
Clay, brown	12	21	
Gravel, compact, med.	21	40	
* Gravel, sand, brown, med.	40	47	
Clay, sand, blue, black, med.	47	65	
* Sand, black, med.	65	79	
Clay, blue	79	81	
* Sandstone, black	81	87	

Work started 1-24 19 79 Completed 1-25 19 79  
Date well drilling machine moved off of well 1-26 19 79

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.  
[Signed] George J. Wainwright Date 1-26, 19 79  
(Drilling Machine Operator)  
Drilling Machine Operator's License No. 837

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.  
Name B & G Drilling  
(Person, firm or corporation) (Type or print)  
Address 10030 S. Mackslung Rd. Conby, Ore.  
[Signed] George J. Wainwright  
(Water Well Contractor)  
Contractor's License No. 637 Date 1-26, 19 79



Oregon Water Resources Department  
 725 Summer Street NE, Suite A  
 Salem Oregon 97301  
 (503) 986-0900  
 www.wrd.state.or.us

# Application for Well ID Number

RECEIVED BY OWRD

NOV 21 2016

Do not complete if the well already has a Well Identification Number.

**I. OWNER INFORMATION**

SALEM, OR

Current Owner Name (please print): SKINNER PROPERTIES, LLC  
 Mailing Address: 1934 N. COUNTRY CLUB DR  
 City, State, Zip: CANBY, OR 97013  
 Mail Well ID Tag to:  SAME AS ABOVE  In Care Of (C/O)  
 Name & Address: \_\_\_\_\_  
 City, State, Zip: \_\_\_\_\_

**II. WELL LOCATION INFORMATION** (Please fill out as completely as possible)

Township: 4 (North/South) Range: 1 (East/West) Section: 5 1/4 of the C 1/4  
 Tax Lot (usually last 3-5 numbers of Tax Map #): 400 County CLACKAMAS  
 GPS Coordinates: LATITUDE: 45.2513 LONG: 122.7167  
 Street Address of Well, City: 25450 S. CASS ST, CANBY, OR 97013  
 If the property had a different street address in the past: 24530 S. CASS ST (I THINK)

**III. GENERAL WELL INFORMATION** (Please fill out as completely as possible, AND attach copy of Well Log, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): COMMERCIAL AGRICULTURE  
 Date Well Constructed (or property built) 1974-75 Total Well Depth: 79' (caved some) Casing Diameter: 6"  
 Owner at time the well was constructed (if known): ALFRED MIJAR Well Log # (if known): \_\_\_\_\_  
 Other Information: \_\_\_\_\_

SUBMITTED BY (please print): STEVE SKINNER PO Box 27 Canby 97013  
 PHONE: 503 701 1806 EMAIL &/or FAX: SKINNERSW@ATT.NET

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902. Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

For Official Use Only by the Oregon Water Resources Department:

Received Date: <u>11-21-16</u>	Well Log Number: <u>CLAC 12922</u>	Well Identification #: <u>L-125024</u>
-----------------------------------	---------------------------------------	---