

APR 13 1990

RECEIVED

CLAC 013

25/4E/24ac
18603

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

MAR 27 1990

SALEM, OREGON

(START CARD) #

(1) OWNER:

Name DAVID FLOOD Well Number: WATER RESOURCES DEPT. 19383 SF
Address 3401 S.E. 12th ST SALEM, OREGON
City Gresham State ORE Zip 97080

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes ☐ No ☒ Depth of Completed Well 340 ft.
Explosives used ☐ Yes ☐ No ☐ Type _____ Amount _____

HOLE		SEAL		Amount	
Diameter	From To	Material	From To	sacks or pounds	
10	0	90 Cement	0	90	30
6	90	350			

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6	1	160	250	☒	☐	☒	☐
Liner:	4	145	340	200	☒	☒	☒	☐

Final location of shoe(s) 160

(7) PERFORATIONS/SCREENS:

☒ Perforations Method SAW
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
340	280	1/8-1/2	400			☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing ☐ Artesian

Yield gal/min	Drawdown	Static stem at	Time
29		300	2 hr.

Temperature of water _____ Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

Township 25 N or S Range 4E E or W, WM.
Section 24B SW 1/4 NE
Tax Lot 2100 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 19383 SF
BAUNTED Rd. SALEM, ORE

(10) STATIC WATER LEVEL:

165 ft. below land surface. Date 3-23-90
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found _____

From	To	Estimated Flow Rate	SWL
280	340	29	165
70	72	5-8	25

(12) WELL LOG:

Ground elevation _____

Material	From	To	SWL
TOP SOIL	0	2	
BROWN CLAY	2	12	
Red CLAY	12	70	25
Cemented GRAVEL	70	129	
SANDSTONE	129	195	
BROWN CLAY	195	208	
SANDSTONE	208	280	
Cemented GRAVEL	280	340	165
BLUE CLAY & SAND	340	350	

Recommended Pump
Setting at 294 to 300 ft.
at NOT more than
25 GPM.

Date started 3-21-90 Completed 3-23-90

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

WWC Number 616
Signed _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 616
Signed _____ Date 3-