

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

RECEIVED
JUL 3 1972

WATER WELL REPORT

STATE OF OREGON

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date of well completion.

STATE ENGINEER
SALEM, OREGON

(Please type or print)

(Do not write above this line)

CLAC

013141
013141

State Well No.

4/1-14 66

State Permit No.

(1) OWNER:

Name Lewis Siri

Address Route 5, Box 710, Oregon City, Or. 97045

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
8" Diam. from 0 ft. to 202 ft. Gage 025
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Mills Knife

Size of perforations 2 in. by 1/4 in.
172 perforations from 97 ft. to 130 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " "
" " " "

Bailer test 50 gal./min. with 5 ft. drawdown after 2 hrs.

Artesian flow g.p.m.

Temperature of water 54° Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Bentonite & puddled clay
Well sealed from land surface to 38 ft.
Diameter of well bore to bottom of seal 12 in.
Diameter of well bore below seal 8 in.
Number of sacks of cement used in well seal sacks
Number of sacks of bentonite used in well seal 2 sacks
Brand name of bentonite National
Number of pounds of bentonite per 100 gallons of water lbs./100 gals.
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? Depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number 47-72
NW 1/4 NW 1/4 Section 11 T. 4S R. 1E W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 91 ft.
Static level 70 ft. below land surface. Date 6/21/72
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 8

Depth drilled 235 ft. Depth of completed well 215 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Clay, brown, sticky	0	5	
Clay, brown, sandy	5	24	
Sand, grey	24	29	
Clay, blue	29	42	
Clay, brown	42	58	
Gravel & boulders	58	69	
Clay, brown, sandy	69	94	
Gravel & sand, loose	94	131	70
Clay, grey	131	160	
Blue clay, sticky	160	179	
Blue, clay, sandy	179	194	
Grey clay, sandy	194	205	
Clay, brown	205	209	
Sand, green, coarse	209	213	
Clay, grey, sticky	213	235	

Work started May 24 1972 Completed June 21 1972

Date well drilling machine moved off of well June 21 1972

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Jack Duus Date 6/28, 1972
(Drilling Machine Operator)

Drilling Machine Operator's License No. 67

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Steinman Bros. (Type or print)
(Person, firm or corporation)

Address 14912 S.E. Kellogg Ave., Milwaukie, Or. 97222

[Signed] Robert E. McConnell
(Water Well Contractor)

Contractor's License No. I Date June 28 1972