

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

WATER WELL REPORT

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

STATE OF OREGON

(Please type or print)
(Do not write above this line)

CLAC

013148

State Well No. 411-14
State Permit No.

AUG 19 1969

G-7267

(1) OWNER:

STATE ENGINEER
SALEM, OREGON

Name RALPH QUINNELL
Address 317 No. LILAC, RIALTO, CALIFORNIA

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

8" Diam. from ± 1 ft. to 18 1/4 ft. Gage 250
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used _____

Size of perforations	in.	by	in.
_____ perforations from _____	_____	_____	_____ ft. to _____ ft.
_____ perforations from _____	_____	_____	_____ ft. to _____ ft.
_____ perforations from _____	_____	_____	_____ ft. to _____ ft.
_____ perforations from _____	_____	_____	_____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WATER LEVEL: Completed well.

Static level 80 ft. below land surface Date 8-7-69
ian pressure _____ lbs. per square inch Date _____

(9) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Driller
Yield: 100 gal./min. with 20 ft. drawdown after 40 hrs.
" " " " " "

Ball test _____ gal./min. with _____ ft. drawdown after _____ hrs.

Artesian flow _____ g.p.m. Date 8-7-69

Temperature of water 54° Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Puddle Clay
Depth of seal 25 ft.
Diameter of well bore to bottom of seal 12 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth _____
Was a drive shoe used? ☒ Yes ☐ No
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.

(11) LOCATION OF WELL:

County CLACKAMAS Driller's well number 12
1/4 1/4 Section 14 T. 45 R. 1E W.M.

Bearing and distance from section or subdivision corner _____

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 200 ft. Depth of completed well 189 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Brown Top Soil	0	2	
Brown Sandy Clay	2	19	
Brown Cement Gravel	19	92	
Brown Sand & Gravel	92	94	80
Blue Cement Gravel	94	138	
Blue Clay	138	189	
Black Sand - Med	189	200	

Work started Aug 2, 1969 Completed 8-7 1969
Date well drilling machine moved off of well 8-8 1969

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] William D. Christenson Date 8-7, 1969
(Drilling Machine Operator)

Drilling Machine Operator's License No. 500

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME William D. Christenson Jr.
(Person, firm or corporation) (Type or print)

Address P.O. Box 343 Hubbard, ORC

[Signed] William D. Christenson Jr.
(Water Well Contractor)

Contractor's License No. 511 Date 8-7, 1969