

CLAC 13152

CLAC

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

WATER WELL REPORT

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

STATE OF OREGON
(Please type or print)

State Well No.

4/1-14 E

State Permit No.

013152

MAR 4 1968

(1) OWNER:

Name John Harmon STATE ENGINEERAddress Rt 3 Box 163
Canby Ore

(2) LOCATION OF WELL:

County Clackamas Driller's well numberSW 1/4 NW 1/4 Section 14 T. 4S R. 1E W.M.

Bearing and distance from section or subdivision corner

240 FT S 160 FT W of the NE Corner
at the SW 1/4 of NW 1/4 of Sec 14 T 4S R 1E

(3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐ Rotary ☐ Driven ☐Irrigation ☐ Test Well ☐ Other ☐ Cable ☐ Jetted ☐Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒

8" Diam. from 0 ft. to 270 ft. Gage 250

" Diam. from ft. to ft. Gage

" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Model No.

Lam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal GroutDepth of seal 30 ft. Was a packer used? No

Diameter of well bore to bottom of seal 9 in.

Were any loose strata cemented off? ☐ Yes ☒ No DepthWas a drive shoe used? ☒ Yes ☐ NoWas well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

(10) WATER LEVELS:

Static level 66 ft. below land surface Date Feb 28 65

Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Driller

Yield: 300 gal./min. with 25 ft. drawdown after 12 hrs.

" " " "

" " " "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 53 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 8"

Depth drilled 330 ft. Depth of completed well 290 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Top Soil	0	3
Brown Clay	3	17
Brown clay & sand	17	24
Blue clay	24	30
Brown clay	30	64
Cement Gravel (Brown)	64	111
Cement Gravel (Blue)	111	126
Cement Gravel (Large)	126	154
Brown clay	154	182
Silt & sand	182	198
Dark Blue clay	198	230
Reddish Brown sand & shale	130	248
Brown silt	248	250
Brown clay	250	270
Reddish brown clay & sand layers (water)	270	305
Green & Gray clay layers	305	321
Black sand & Gray clay layers (water)	321	330
Fine sand was developed from sand layers until clear water at 300 ft		

Work started 2 15 1968 Completed 2-28 1968

Date well drilling machine moved off of well 2-28 1968

(13) PUMP:

Manufacturer's Name

Type: Submersible H.P. 1 hp

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME John W. Beck Well Drilling

(Person, firm or corporation)

(Type or print)

Address 954 S. Hwy 51 Canby OreDrilling Machine Operator's License No. 437[Signed] John W. Beck

(Water Well Contractor)

Contractor's License No. 4419 Date Feb 28, 1968