

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

RECEIVED

APR 3 1973

State Well No.

45/2E-2

STATE ENGINEER

State Permit No.

G-6194

SALEM, OREGON

G-6613

(1) OWNER:

Name ROBERT LEHMAN
Address S. NEWKERCHNER ROAD
OREGON CITY, OREGON

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

6" Diam. from 0 ft. to 38 ft. Gage 17.05
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " " " "

Bailer test 54 gal./min. with 37 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water 48 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used CEMENT
Well sealed from land surface to 38 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 10 sacks
Number of sacks of bentonite used in well seal NONE sacks
Brand name of bentonite
Number of pounds of bentonite per 100 gallons
of water lbs./100 gals.
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth ft. strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County CLACKAMAS Driller's well number
SW 1/4 NW 1/4 Section 2 T. 4S R. 2E W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 65 ft.
Static level 24 ft. below land surface. Date 3/30/73
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 112 ft. Depth of completed well 112 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL	0	3	
RED CLAY	3	14	
LIGHT GREY SOFT	14	30	
LAVA	30		
MED GREY LAVA	30	65	24
SOFT HONEY COMED	65	67	
MED GREY LAVA	67	88	W.B.
SOFT HONEY COMED	88	102	
SOFT YELLOW SANDSTONE	102	112	

Work started 3/27 1973 Completed 3/30 1973
Date well drilling machine moved off of well 3/31 1973

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] William J. Stennett Date 4/2, 1973
(Drilling Machine Operator)

Drilling Machine Operator's License No. 170

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name WILLIAM J. STENNETT
(Person, firm or corporation) (Type or print)

Address 361 WARNER MILNE RD. OREGON CITY

[Signed] William J. Stennett
(Water Well Contractor)

Contractor's License No. 5 Date 4/2, 1973