

WATER WELL REPORT  
STATE OF OREGON

CLAC

013530

RECEIVED

FEB 8 1983

WATER RESOURCES DEPT.  
SALEM, OREGON

State Well No. 45/2E-3dc

State Permit No.

(1) OWNER:

Name GARY + CLAUDIA BARNETT  
Address 15750 S. WROSTAD DR.  
City OREGON CITY State ORE

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐  
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐  
Rotary Mud ☐ Dug ☐ Irrigation ☐ Test Well ☐ Other ☐  
e ☐ Bored ☐ Thermal: Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED: Steel ☒ Plastic ☐  
Threaded ☐ Welded ☒  
6 5/8" Diam. from +2 ft. to 198 ft. Gauge 250  
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

4" Diam. from 190 ft. to 270 ft. Gauge PVC

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used SKIL SAW  
Size of perforations 6 in. by 1/8 in.  
30 perforations from 260 ft. to 270 ft.  
perforations from ft. to ft.  
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name  
Type Model No.  
Diam. Slot Size Set from ft. to ft.  
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?  
Field: gal./min. with ft. drawdown after hrs.  
Air test 20 gal./min. with drill stem at 265 ft. 2 hrs.  
Bailer test gal./min. with ft. drawdown after hrs.  
Artesian flow g.p.m.  
Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used CEMENT  
Well sealed from land surface to 30' ft.  
Diameter of well bore to bottom of seal 10 in.  
Diameter of well bore below seal 6 in.  
Number of sacks of cement used in well seal 14 sacks  
How was cement grout placed? GROUTED

Was pump installed? NO Type HP Depth ft.  
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.  
Did any strata contain unusable water? ☐ Yes ☒ No  
Type of Water? depth of strata  
Method of sealing strata off  
Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.  
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County CLACKAMAS Driller's well number  
SW 1/4 SE 1/4 Section 3 T. 45 R. 2E W.M.  
Tax Lot # Lot Blk Subdivision  
Address at well location:

(11) WATER LEVEL: Completed well.

Depth at which water was first found 96 ft.  
Static level 200 ft. below land surface. Date 2/10/83  
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 270 ft. Depth of completed well 270 ft.  
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

| MATERIAL             | From | To  | SWL |
|----------------------|------|-----|-----|
| TOP SOIL             | 0    | 2   |     |
| Clay Brown           | 2    | 18  |     |
| Claystone Gray       | 18   | 96  |     |
| Gravel Cemented      | 96   | 108 |     |
| Clay Gray Sand Black | 108  | 185 |     |
| Claystone Blue       | 185  | 260 |     |
| Sandstone Brown      | 260  | 268 |     |
| Clay blue            | 268  | 270 |     |

Work started 2-8 19 83 Completed 2-10 1983  
Date well drilling machine moved off of well 2-10 1983

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.  
[Signed] Mary W. Barnett Date 2-10 1982  
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1038

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Barnett Drilling & Pumps, Inc.  
(Person, firm or corporation) (Type or print)  
Address 15750 S. Wrosted Dr. One City  
[Signed] Mary W. Barnett (Water Well Contractor)  
Contractor's License No. 164 Date 2-10 1983

NOTICE TO WATER WELL CONTRACTOR  
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,  
SALEM, OREGON 97310  
within 30 days from the date of well completion.

SP\*12658-690