

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

RECEIVED

WATER WELL REPORT

CLAG

STATE OF OREGON

(Please type or print)

STATE ENGINEER, SALEM, OREGON 97301

within 30 days from the date

of well completion. (Do not write above this line)

WATER RESOURCES DEPT.

SALEM, OREGON

State Well No. 45/2E-5

State Permit No.

(1) OWNER:

Name Anderson Ritter
Address 255 S.W. 1st. Ave.
Canby, Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☐

6" Diam. from 0 ft. to 70 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " " " "

Bailer test 16 gal./min. with 22 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water 54 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Bentonite
Well sealed from land surface to 38 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal sacks
Number of sacks of bentonite used in well seal 14 sacks
Brand name of bentonite Oregon
Number of pounds of bentonite per 100 gallons of water 200 lbs./100 gals.
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number
1/4 1/4 Section 5 T4S R. 2E W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 187 ft.
Static level 97 ft. below land surface. Date 8-25-77
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 202 ft. Depth of completed well 200 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil & red	0	2	
Clay & boulders red	2	31	
Clay red	31	60	
Clay w-gravel grey	60	69	
Rock grey	69	102	
Clay grey	102	124	
Sandstone grey	124	135	
Clay blue (hard)	135	185	
Clay grey (hard)	185	187	
Clay-sandy grey W.B.	187	202	97

Work started 8-16 1977 Completed 8-24 1977
Date well drilling machine moved off of well 8-25 1977

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Robert A. Stites Date 8-25, 1977
(Drilling Machine Operator)

Drilling Machine Operator's License No. 776

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

A C Stites
Name (Person, firm or corporation) (Type or print)

Address 28290 S. Dryland Rd. Canby, Oregon

[Signed] A.C. Stites (Water Well Contractor)

Contractor's License No. 533 Date August 25, 1977