

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

01402 WATER WELL REPORT

STATE OF OREGON

RECEIVED

JUN 4 1981

State Well No.

155E-3399

(Please type or print)

WATER RESOURCES DEPT

State Permit No.

SALEM, OREGON

(1) OWNER:

Name SHAYNE BOWKER
Address Route 1 Box 1750
Corbett, Oregon 97019

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
6 5/8 Diam. from 0 ft. to 125 ft. Gage .250
4 1/2 Diam. from 0 ft. to 350 ft. Gage .200
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used SAW
Size of perforations 1/8 in. by 7 in.
65 perforations from 310 ft. to 350 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? driller
Yield: 10 gal./min. with 51 ft. drawdown after 1 hrs.

Baller test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.

Temperature of water 51 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement grout
Well sealed from land surface to 18 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 12 sacks
How was cement grout placed? pressure grout from
bottom of starter hole to land surface

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number 7918
NE 1/4 NE 1/4 Section 33 T. 1S R. 5E W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 340 ft.
Static level 279 ft. below land surface. Date 7/16/79
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"
Depth drilled 350 ft. Depth of completed well 350 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil brown	0	1	
Clay brow/sm boulders	1	25	
Rock gray brown soft	25	33	
Clay brown	33	51	
Clay brown/sm boulders	51	55	
Clay brown	55	67	
Rock brown soft	67	71	
Clay brown	71	98	
Rock gray soft	98	120	
Rock gray med	120	136	
Rock red brown soft	136	142	
Rock gray med	142	167	
Rock gray brown med	167	330	
Cemented gravel	330	350	

Work started 7/10/79 19 Completed 7/16/79 19
Date well drilling machine moved off of well 7/17/79 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Ross A. Jannsen Date 8/12/79, 19
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1334

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Ross A. Jannsen Well Drilling
(Person, firm or corporation) (Type or print)
Address Rt. 1 Box 485 Estacada, Ore. 97023

[Signed] Ross A. Jannsen
(Water Well Contractor)

Contractor's License No. 483 Date 8/12/79, 19