

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

RECEIVED

WATER WELL REPORT

RECEIVED

MAR 17 1976

STATE OF OREGON

MAR 5 - 1976

State Well No.

35/4E-36

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date
of well completion.

WATER RESOURCES DEPT.
SALEM, OREGON

(Type or print)

not write above this line

WATER RESOURCES DEPT.
SALEM, OREGON

State Permit No.

CLAC
015018

(1) OWNER:

Name Al Smith Davis
Address 515 SE Renae St 5012
Gresham, Ore.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Pur ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

6" Diam. from 0 ft. to 97 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Torch

Size of perforations 3/8" in. by 6 in.
32 perforations from 80 ft. to 97 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test 9 gal./min. with 60 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water 52 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement & Bentonite

Well sealed from land surface to 90 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 3 sacks

Number of sacks of bentonite used in well seal 5 sacks

Brand name of bentonite Bonard

Number of pounds of bentonite per 100 gallons

of water 50 lbs./100 gals.

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number
Section 36 T. 3S R. 4E W.M.

Bearing and distance from section or subdivision corner

4.6 acres commonly known as
Rt 3 Box 856 Estacada Ore.

(11) WATER LEVEL: Completed well.

Depth at which water was first found 50 ft.

Static level 20 ft. below land surface. Date 7-1-75

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 97 ft. Depth of completed well 97 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL	0	2	
Red Clay	2	32	
Brown Clay	32	48	
TAN CLAY SANDY	48	55	16
SHALE-GRAY	55	75	
Clay TAN SANDY	75	95	20
Clay Bright Red	95	97	

Work started 6-10 1975 Completed 6-20 1975

Date well drilling machine moved off of well 6-22 1975

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] John D. McChally Date 7-1, 1975
(Drilling Machine Operator)

Drilling Machine Operator's License No. 662

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name John D. McChally Well Drilling
(Person, firm or corporation) (Type or print)

Address Rt 3 Box 551 Estacada Ore

[Signed] John D. McChally
(Water Well Contractor)

Contractor's License No. 547 Date 7-1-75, 1975