

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON
within 30 days from the date of well completion.

RECEIVED
JUL 11 1967

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

SALEM OREGON

State Well No. 312-29 B

State Permit No. G-4035

(1) OWNER:

Name ELDON C. EVANS
Address RT 3 BOX 261 OREGON CITY

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
8" Diam. from 0 ft. to 500 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used TORCH
Size of perforations 3/8 in. by 12 in.
480 perforations from 40 ft. to 500 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____ Model No. _____
Type _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WATER LEVEL: Completed well.

Static level 93 ft. below land surface Date 5/29
Artesian pressure _____ lbs. per square inch Date _____

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? DRILLER
1: 250 gal./min. with 52 ft. drawdown after 6 1/2 hrs.
" " " " " " " "

Bailer test _____ gal./min. with _____ ft. drawdown after _____ hrs.
Artesian flow _____ g.p.m. Date _____
Temperature of water _____ Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used CEMENT & BENTONITE
Depth of seal 20 FT ft.
Diameter of well bore to bottom of seal 12 1/4 in. to 500 FT
Were any loose strata cemented off? ☐ Yes ☒ No Depth _____
Was a drive shoe used? ☐ Yes ☒ No
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? ☒ Yes ☐ No Size of gravel: 3/4
Gravel placed from 20 ft. to 500 ft.

(11) LOCATION OF WELL:

County CLACKAMAS Driller's well number _____
1/4 1/4 Section T. R. W.M.

Bearing and distance from section or subdivision corner
2500 FT W. & 600 FT S. OF N.E COR
SEC 29 T-3-S. R. 2 E

(12) WELL LOG:

Diameter of well below casing NONE

Depth drilled 500 ft. Depth of completed well 500 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
TOP SOIL RED	0	1	
CLAY RED	1	17	
SOFT SANDSTONE BRN	17	21	
MED BASALT BLK	21	25	
CLAY BRN.	25	34	
MED SANDSTONE BRN	34	91	W.B.
MED CLAY STONE GRAY	91	118	
SOFT SANDSTONE BRN	118	155	
CLAY BLUE	155	243	
CLAY GREY SANDY	243	268	
" BLUE "	268	356	
M. SANDSTONE GRAY	356	359	
CLAY GREEN	359	383	
111' SANDY, GREY	383	402	
ROTTEN LOG BRN	402	409	
CLAY SANDY GREY	409	487	
" & GREEN			
CLAY GREEN	487	500	
STICKY			

Work started 5/8 1967 Completed 6/3 1967

Date well drilling machine moved off of well 6/3 1967

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Paul R. Stadel Date 7-11, 1967
(Drilling Machine Operator)

Drilling Machine Operator's License No. 16-322

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME R. STADELI & SONS (Type or print)

Address RT 3 BOX 169 SILVERTON.

[Signed] Paul R. Stadel (Water Well Contractor)

Contractor's License No. 296 Date 7/10, 1967