

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

CLAG WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

RECEIVED

NOV 28 1975

WATER RESOURCES DEPT.

SALEM, OREGON

State Well No. 35/3E-4 CC

35/3E-4 CC

Permit No.

(1) OWNER:

Name William T. Jones
Address 16831 South Holcomb
Oregon City, Oregon 97045

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

6 5/8" Diam. from 0 ft. to 160 ft. Gage .250
4 1/2" Diam. from 158 ft. to 185 ft. Gage 10
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.
Type of perforator used torch
Size of perforations 3/8 in. by 12 in.
12 perforations from 167 ft. to 183 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level
Was a pump test made? ☒ Yes ☐ No If yes, by whom? driller
Yield: 10 gal./min. with 27 ft. drawdown after 1 hrs.
" " " "
" " " "
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water 51 Depth artesian flow encountered ft.

(9) CONSTRUCTION: Cement

Well seal—Material used Bentonite, pud. clay
Well sealed from land surface to 38 ft.
Diameter of well bore to bottom of seal 9 5/8 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 1 sacks
Number of sacks of bentonite used in well seal 50# sacks
Brand name of bentonite National
Number of pounds of bentonite per 100 gallons
of water 1:5 ratio lbs./100 gals.
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number 769
SE 1/4 SE 1/4 Section 4 T. 3S R. 3E W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 173 ft.
Static level 158 ft. below land surface. Date 8/6/75
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"
Depth drilled 185 ft. Depth of completed well 185 ft.
Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil brown	0	1	
Clay brown	1	6	
Consolidated conglomerate	6	28	
Clay yellow	28	40	
Clay gray	40	66	
Sandstone gray soft	66	67	
Clay gray	67	115	
Sandstone brown soft	115	123	
Claystone brown	123	128	
Sandstone brown soft	128	133	
Clay brown	133	134	
Clay gray	134	141	
Claystone green	141	143	
Sandstone gray soft	143	185	

Work started 8/1/75 19 Completed 8/6/75 19
Date well drilling machine moved off of well 8/6/75 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Ross Janssen Date 8/6/75, 19____
(Drilling Machine Operator)

Drilling Machine Operator's License No. 399

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Ross Janssen Well Drilling
(Person, firm or corporation) (Type or print)

Address Rt. 1 Box 485 Estacada, Oregon 97021

[Signed] Ross Janssen
(Water Well Contractor)

Contractor's License No. 433 Date 8/6/75, 19____