

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion

RECEIVED

MAY 22 1979

STATE OF OREGON
(Please type or print)

(Do not write above this line)

WATER RESOURCES DEPT.

SALEM, OREGON

State Well No. 35/3E-23

State Permit No.

(1) OWNER:

Name BEN GIRMUS
Address RT 2 BOX 928 Estacada Ore 97123

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

6" Diam. from 0 ft. to 76 ft. Gage 250
4" Diam. from 35 ft. to 65 ft. Gage 188
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used SAW

Size of perforations 1/8 in. by 6 in.
45 perforations from 46 ft. to 65 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " "

Bailer test 13 gal./min. with 20 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water 52 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement grout
Well sealed from land surface to 30 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 13 sacks
How was cement grout placed? Cement was placed
as 8" starter pipe was being
removed
30 FT 8" starter pipe
Was a drive shoe used? ☐ Yes ☐ No Plugs Size location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clack Driller's well number
1/4 1/4 Section 23 T. 3S R. 3E W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 119 ft.
Static level 31 ft. below land surface. Date
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6
Depth drilled 65 ft. Depth of completed well 65 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL	0	2	0
Yellow clay	2	21	0
Cemented gravel	21	49	80
SAND & GRAVEL W.B.	49	56	30
SANDSTONE Yellow	56	65	30

Work started 5/1/79 1979 Completed 5/11/ 1979

Date well drilling machine moved off of well 5/11/ 1979

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Brad Brant Date 5/14, 1979
(Drilling Machine Operator)

Drilling Machine Operator's License No. 861

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Lanz Well Drilling
(Person, firm or corporation) (Type or print)

Address 15702 S. Neighbor Rd Oregon City

[Signed] Donald H. Lanz
(Water Well Contractor)

Contractor's License No. 565 Date 5-14, 1979