

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

FEB - 7 1992

(START CARD) #

2s/4e/15
38199

(1) OWNER:

Name DON JONES Well Number _____
Address 30445 E SPRING HILL RD.
City CORBETT State OR, Zip _____

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD:

☐ Rotary Air ☐ Rotary Mud ☒ Cable
☐ Other _____

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 257 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
12	30	0	BENTONITE	0	30	17
8	30	257				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☐ Other FORED

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from 208 ft. to 257 ft. Size of gravel 1/4"

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8"	+1	220	250	☒	☐	☒	☐
Liner:	6	208	257		☐	☒	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☒ Perforations Method SKILL SAW
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
220	255		200	6"x1/8"		☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☒ Bailor ☐ Air ☐ Flowing
☐ Artesian

Yield gal/min	Drawdown	Drill stem at	Time
32	6		1 hr.

Temperature of Water 56° Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County CLACKAMAS Latitude _____ Longitude _____
Township 2S N or S. Range 4E E or W. WM. _____
Section 15 1/4 _____ 1/4 _____
Tax Lot 1200 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) SLOGAN RD.
SANDY OREGON

(10) STATIC WATER LEVEL:

175 ft. below land surface. Date 1/7/92
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 227

From	To	Estimated Flow Rate	SWL
227	251	100 GPM	175

(12) WELL LOG:

Ground elevation _____

Material	From	To	SWL
TOP SOIL	0	1	
RED CLAY	1	27	
BROWN CLAY, SOME GRAVEL	27	126	
FINE BROWN SAND	126	130	
BROWN SILTY CLAY	130	149	
GRAY SANDSTONE	149	158	
GRAY SILTY CLAY	158	163	
GRAY SANDSTONE	163	177	
CEMENTED GRAVEL	177	185	
BROWN SILTY CLAY	185	204	
RED CLAY	204	209	
YELLOW CLAY	209	217	
BLACK SANDSTONE	217	251	175
BROWN CLAY	251	257	

Date started 12/20/91 Completed 1/7/92

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed [Signature] WWC Number 462
Date 2/2/92