

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

CLAC 17946
Skyles Drilling, Inc.
1169 Molalla Ave.
Oregon City, OR 97045

JUN 18 1992

25/6E/19cc

DEPT. OF LAND & FOREST (START CARD) # 40158
SALEM, OREGON

(1) OWNER:

Well Number 02

Name Emmert Industrial Corp. (Terry Emmert)

Address 11811 S.E. Hwy 212

City Clackamas State OR Zip 97015

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable

☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation

☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 205 ft.

Explosives used ☐ Yes ☒ No Type Amount

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
10	0	18	Gran. Bent.	0	18	9 sacks
6	18	205				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other Granular Bentonite placed dry

Backfill placed from ft. to ft. Material

Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6	+1	19	.250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:	4	9	205	160	☐	☒	☒	☐
					☐	☐	☐	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Saw

☐ Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
186	204	1/8-2	160			☐	☒
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing
☐ Artesian

Yield gal/min	Drawdown	Drill stem at	Time
33		204	1 hr.
25		192	1/2 hr.

Temperature of Water 53° Depth Artesian Flow Found

Was a water analysis done? ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County Clackamas Latitude Longitude

Township 2S N or S. Range 6E E or W. WM.

Section 19 SW 1/4 SW 1/4

Tax Lot 1800 Lot Block Subdivision

Street Address of Well (or nearest address) 52525 SE Cherryville
Drive, Sandy, Oregon

(10) STATIC WATER LEVEL:

119 ft. below land surface. Date 6-6-92

Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 178

From	To	Estimated Flow Rate	SWL
178	204	33	119

(12) WELL LOG:

Ground elevation

Material	From	To	SWL
Clay Brown Sandy	0	8	
Lava Brown	8	16	
Lava Gray	16	178	
Lava Red	178	186	
Lava Brown	186	192	
Lava Gray Fractured	192	204	119
Lava Gray	204	205	

Date started 6-6-92 Completed 6-6-92

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed Norm R. Edie WWC Number 1547
Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to my knowledge and belief.

Signed Marni D. Skyles WWC Number 553
Date 6-12-92