

16
STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

RECEIVED
APR 14 1993

WATER RESOURCES DEPT.

(START CARD) # 45257

(1) OWNER:

Name Mark & Debbie Eisen Zimmer
Address 24141 S.E. BORGES RD
City Gresham State OR Zip 97030

Well Number

(2) TYPE OF WORK:

☐ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD:

☐ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 500 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE		SEAL				Amount sacks or pounds
Diameter	From To	Material	From To			
14	0 25	Cement	0 75			60
10	200 300	Cement	200 300			30
8	25 200					
8	300 500					

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8	0	300	250	☒	☐	☒	☐
	6	200	500	250	☒	☐	☒	☐
Liner:	6	200	500	250	☒	☐	☒	☐

Final location of shoe(s) 300

(7) PERFORATIONS/SCREENS:

☒ Perforations Method AIR KNIFE
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
400	500	1/8-2	2400	6	PIPE	☒	☒
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
400		460	4 hr.

Temperature of Water 56 Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County CLATSOP Latitude _____ Longitude _____
Township 1S N or S. Range 4E E or W. WM. _____
Section 29 1/4 _____ 1/4 _____
Tax Lot 600 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) NE CORNER
WAYBELL & ORIENT DRIVE GRESHAM

(10) STATIC WATER LEVEL:

198 ft. below land surface. Date 3-12-93
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 300

From	To	Estimated Flow Rate	SWL
300	500	400	198

(12) WELL LOG:

Ground elevation _____

Material	From	To	SWL
TOP SOIL	0	4	
CLAY BRN	4	23	
ROCK WEATH. BRN CLAY BRN	23	70	
GRAVEL MED. GRAY W/STONES	70		
OF SAND STONE		168	
FINE CEMENTED GRAVEL	168	300	
FINE CEMENTED GRAVEL	300		
WITH BANGOR GRAVEL			
WATER BEARING			
FINE CEMENTED GRAVEL	460		
WITH SEAMS OF BLUE CLAY		500	

RECEIVED

MAY 24 1993

WATER RESOURCES DEPT.
SALEM, OREGON

Date started 2-18-93 Completed 3-12-93

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed Ed Pulliam WWC Number 666
Date 4-10-93