

16
STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

RECEIVED
AUG 18 1993
WATER RESOURCES DEPT. (START CARD) # 47738
SALEM, OREGON

(1) OWNER:

Well Number _____
Name PETER EFIMOV/JOSEPH NOVAK
Address 1314 S. EBY RD.
City CANBY State OR Zip 97013

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD:

☐ Rotary Air ☐ Rotary Mud ☒ Cable
☐ Other _____

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 146 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
10	0	32	CEMENT	0	32	25 SACKS
6	32	147				

BENTONITE GRANULAR PLACED IN TOP 1 FT.

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other _____

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1.5	146	.250	☒	☐	☒	☐
				☐	☐	☐	☐
				☐	☐	☐	☐
Liner:				☐	☐	☐	☐
				☐	☐	☐	☐

Final location of shoe(s) 146

(7) PERFORATIONS/SCREENS:

☒ Perforations Method MILLS KNIFE
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
78	142	3/8x3	360			☒	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump ☐ Bailer ☐ Air ☐ Flowing
☐ Artesian

Yield gal/min	Drawdown	Drill stem at	Time
			1 hr.
43	31		3 HRS

Temperature of Water 55 Depth Artesian Flow Found _____
Was a water analysis done? ☐ Yes By whom NO
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County CLACKAMAS Latitude _____ Longitude _____
Township 4S N or S. Range 1E E or W. WM.
Section 36 NE $\frac{1}{4}$ NW $\frac{1}{4}$
Tax Lot 400 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 11314 S. EBY RD.
CANBY, OR

(10) STATIC WATER LEVEL:

20 ft. below land surface. Date 7-15-93
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 11

From	To	Estimated Flow Rate	SWL
11	22	U/K	5
64	147		20

(12) WELL LOG:

Ground elevation _____

Material	From	To	SWL
TOP SOIL	0	1	
CLAY BROWN	1	11	
CLAY BROWN SILTY	11	14	
CLAY GREY SILTY	14	22	
CLAY BLUE	22	28	
CLAY BLUE W/GRAVEL	28	31	
GRAVEL W/CLAY BRN	31	63	
CLAY BRN	63	64	
GRAVEL CEMENTED	64	80	
GRAVEL LOOSLY CEMENTED	80	84	
GRAVEL CEMENTED	84	111	
CLAY BRN	111	112	
GRAVEL CEMENTED	112	134	
CLAY TAN	134	136	
GRAVEL & CLAY	136	147	

Westerberg Drilling, Inc.
36728 S. Kropf Rd.
Molalla, OR 97038
829-2526

Date started 7-1-93 Completed 7-15-93

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

WWC Number _____
Signed _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 688
Signed Steven M. Shadish Date 7-31-93