

is true to the best of my knowledge and belief.

Signed Richard Burt WWC Number 743
Date Mar 28, 98

1. Owner: Rodney B Smith
6414 s Zimmerman rd. **CLAC 20184**
Canby OR 97013



2. New Well
3. Cable
4. Proposed use: Domestic & Irrigation
5. Depth of completed well: 377
12" 0-30, 8" 30-377
Seal Material: Granular 0-30 ft. 22 sacks
Method: Granular Bentonite Method
6. Casing: 8" 0-377, .250, steel/welded
7. Perforations: 354-372, 1/8 slot size, #500
8. Well Test: Air, 180 gpm, drill stem 210, 2 hrs
9. Clac, 4S, 1E, 30bc, street of well: 6414 s Zimmerman Rd Canby
10. SWL: 62 ft, 3/3/95
11. First water: 50, from 55 to 377, SWL 62 ft.
12. Well log:
13. Soil

	1-3
Clay, brown	3-55
Clay brown w/sand	55-98
Clay grey w/ sand layers	98-161
Sand, black small gravel	161-169
Clay, blue	166-177
Clay, grey	177-208
Clay, tan	208-261
Sand, fine black	261-266
Clay, grey	266-354
Sand & gravel black	354-370
Clay, blue	370-377

Start date: 1/20/95

end date: 3/3/95

Constructor: #743