

(1) OWNER: Well No. 05011995
Name HUGH & MARI-DEAN EISELE
Address 8620 SE 347 TH AVE
City BORING St OR Zip 97009

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: IRRIGATION

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO Depth of Compl. Well 480 ft
Explosives used NO Type Amount

HOLE			SEAL			
Diam.	From	To	Material	From	To	Amount
14	0	86	CEMENT	0	86	33 SACKS
10	86	240	CEMENT	180	240	45 SACKS
9 5/8	240	480				

Seal placement method C

Backfill: from ft to ft Material
Gravel: from ft to ft Size

(6) CASING/LINER:

	Diam.	From	To	Gauge	Material	Connection
Casing	10	+1	86	250	STEEL	WELDED
	8	0	480	250	STEEL	WELDED

Liner

Final Location of shoe(s) 480' 7 1/2 TUBEX

(7) PERFORATIONS/SCREENS:

[X] Perf. Method AIR KNIFE

[] Screens Type Material

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
380	400	1/8X2	720			CASING
420	470	1/8X2	1500			CASING

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
100		480	1 hr.
150	64		8HR/PUMP

Temperature of water 50F Depth Artesian Flow Found
Was water analysis done? NO By whom
Reason for water not suitable for use
Depth of strata

(9) LOCATION OF WELL by legal description:

County CLACK Lat. ° ' " Long. ° ' "
Township 1 S Range 4 E WM.
Section 27 NE 1/4 NW 1/4
Tax Lot Lot Block Subdivision
Street Address of Well (or nearest Address)
8620 SE 347TH AVENUE BORING, OR 97009

(10) STATIC WATER LEVEL:

296 ft. below land surface. Date 04/02/95
Artesian pressure lb per square in. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 30		Est Flow Rate	SWL
From	To		
30	50	20+GPM	28
340	470	150GPM	296

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
TOP SOIL	0	2	
BROWN CLAY	2	30	
CLAY & GRAVEL	30	70	28
CEMENTED GRAVEL	70	240	
LIGHTLY CEMENTED GRAVEL	240	400	296
SAND & GRAVEL	400	420	296
LIGHTLY CEMENTED GRAVEL	420	470	296
BLUE CLAY	470	480	

Date started 02/24/95

Completed 04/02/95

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed WWC Number
Date

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed WWC Number 616
Date 05/01/95