


(as required by ORS 537.765)

MAY 23 1995

~~SALEM, OREGON~~

Well Number

ORIGINAL & FIRST COPY-WATER RESOURCES DEPARTMENT SECOND COPY-CONSTRUCTOR THIRD COPY-CUSTOMER



CLAC
20274

MEADOWCROFT FARM
15568 S. CARUS RD.
OREGON CITY, OR 97045
CLACKAMAS CO. 97045
T3S R2E SEC.34 SW NE
START CARD #51406

3s/2e/34ac RECEIVED


MAY 23 1995

WATER RESOURCES DEPT.
SALEM, OREGON

36728 S. Kropf Rd., Molalla, OR 97038 • Phone: (503) 829-2526 FAX (503) 829-7514

FORMATION LOG:

MATERIAL	FROM	TO
top soil	0	1
clay red	1	12
clay red w/soft decomposed		
brown rock	12	17
boring lava grey	17	41
clay brown gritty	41	60
clay tan sticky	60	66
sandstone grey/brown	66	74
sandstone, gravel brown/grey		
w/streaks of siltstone & clay		
brown	74	101
caly tan	101	122
clay grey	122	163
clay tan	163	227
clay tan w/some gravel sticky	227	244
course sand, fine gravel &		
pumice loosely cemented	244	260
clay tan	260	282
clay grey	282	297
clay blue/green	297	299
clay grey	299	386
clay blue	386	400
clay grey	400	412
clay blue	412	426
clay grey w/intermittent soft		
grey siltstone lenses	426	438
clay blue	438	466
clay grey	466	524
clay grey w/thin lenses of		
soft grey siltstone	524	536
clay grey sticky w/mica	536	561
silty sand w/mica	561	579
clay grey	579	609
clay w/mica soft	609	618
clay grey	618	626
fine grey silty sand w/grey/		
white pumice	626	637
clay brown	637	652
clay grey	652	671
sand black med.	671	677
clay blue/grey	677	683
course sand fine gravel		
loosely cemented	683	696
clay grey w/layers of blue		
crumbly clay	696	733



CLAC
20274

MEADOWCROFT FARM
15568 S. CARUS RD.
OREGON CITY, OR 97045
CLACKAMAS
T3S R2E SEC.34 SW NE
START CARD #51406

35/26/34 ac RECEIVED

MAY 23 1995

WATER RESOURCES DEPT.
SALEM, OREGON

36728 S. Kropf Rd., Molalla, OR 97038 • Phone: (503) 829-2526 FAX (503) 829-7514

FORMATION LOG:

MATERIAL	FROM	TO
course sand fine gravel w/thin lenses of siltstone	733	740
clay blue	740	742
course sand fine gravel	742	751
clay grey dark	751	782
clay grey blue w/thin lenses of siltstone soft sandstone	782	877
clay blue crumbly	877	894
clay grey green sticky	894	906
clay grey & blue sticky	906	1104
clay grey gritty	1104	1162
clay blue sticky	1162	1174
clay red/brown sticky	1174	1218
clay layers, grey/brown/green/white blue sticky w/pieces of black wood	1218	1238
clay blue/green	1238	1258
basalt grey	1258	1260
clay	1260	1262
basalt grey	1262	1280
basalt grey slightly fractured w/brown	1280	1284 WB
basalt grey hard	1284	1318
basalt grey w/green & red porous broken	1318	1336 WB
basalt grey hard	1336	1346
basalt grey/green broken porous	1346	1351
basalt grey hard	1351	1353
basalt grey/green broken w/ weathered seams & some grey shale or claystone	1353	1369
basalt grey hard	1369	1374
basalt grey w/blue & red broken, porous	1374	1392
basalt grey w/trace of brn/broken	1392	1397
basalt grey hard	1397	1408
basalt grey w/trace of brown fractured	1408	1428 WB
basalt grey med hard	1428	1471
basalt grey w/brown broken & decomposed	1471	1500