

STATE OF OREGON WATER SUPPLY WELL REPORT

OCT - 9 1995

WATER RESOURCES DEPT. 656-2683

(START CARD) # 82888

Instructions for completing this report are on the last page of this form

(1) OWNER: Well Number 01 Name Peter Kusyk/Beacon Homes Address 9500 SW 125th Ave. City Beaverton State Or. Zip 97008

(2) TYPE OF WORK [X] New Well [] Deepening [] Alteration (repair/recondition) [] Abandonment

(3) DRILL METHOD: [X] Rotary Air [] Rotary Mud [] Cable [] Auger [] Other

(4) PROPOSED USE: [X] Domestic [] Community [] Industrial [] Irrigation [] Thermal [] Injection [] Livestock [] Other

(5) BORE HOLE CONSTRUCTION: Special Construction approval [] Yes [X] No Depth of Completed Well 384 ft. Explosives used [] Yes [X] No Type Amount

Table with columns for HOLE Diameter, From, To, Material, and SEAL From, To, Sacks or pounds. Row 1: 10", 0, 59, Cem Bent, 59, 0, 14 sacks. Row 2: 6", 59, 384.

How was seal placed: Method [] A [] B [X] C [] D [] E [] Other

Backfill placed from ft. to ft. Material Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Table with columns for Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Casing: 6", +1, 59, 250, [X], [], [X], []. Liner: 4", 4, 384, 160#, [], [X], [X], [].

Final location of shoe(s) None

(7) PERFORATIONS/SCREENS: Table with columns for From, To, Slot size, Number, Diameter, Material, Tele/pipe size, Casing, Liner. Row 1: 365, 383, 1/8x3, 80, [], [], [], [X].

(8) WELL TESTS: Minimum testing time is 1 hour. Table with columns for Pump, Bailer, Air, Artesian, Yield gal/min, Drawdown, Drill stem at, Time. Row 1: 100, 380, 1 hr. Row 2: 75, 354, 1/2.

Temperature of water 55° Depth Artesian Flow Found Was a water analysis done? [] Yes By whom Did any strata contain water not suitable for intended use? [] Too little [] Salty [] Muddy [] Odor [] Colored [] Other Depth of strata:

(9) LOCATION OF WELL by legal description: Count Clackamas Latitude Longitude Township 2 South N or S Range 1 East E or W. WM. Section 31 SW 1/4 NW 1/4 Tax Lot 705 Lot 1 Block Subdivision Street Address of Well (or nearest address) 6401 SW Meridian Way Tualatin, Or.

(10) STATIC WATER LEVEL: 225 ft. below land surface. Date 10-2-95 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Table with columns for From, To, Estimated Flow Rate, SWL. Row 1: 296', 381', 100, 225.

(12) WELL LOG: Ground Elevation

Table with columns for Material, From, To, SWL. Rows include Clay Brown, Basalt Gray & Brown, Basalt Gray Hard, Basalt Gray, Basalt Red Porous, Basalt Brown & Gray, Basalt Gray, Basalt Gray & Brown, Basalt Gray, Basalt Gray & Brown, Basalt Gray, Basalt Gray Fractured, Basalt Gray & Brown, Basalt Gray Fractured, Basalt Black Porous, Basalt Black.

Date started 9-29-95 Completed 10-2-95 (unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed [Signature] WWC Number 553 Date 10-4-95

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed [Signature] WWC Number 1592 Date 10-4-95