

WATER WELL REPORT
STATE OF OREGON

9-26

(1) OWNER:

Name Bill Schwabauer
Address 8407 S. Barnards Rd
City CANBY State ORE

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Air ☐ Driven ☐ Domestic ☐ Industrial ☐ Municipal ☐
Mud ☐ Dug ☐ Irrigation ☒ Test Well ☐ Other ☐
Cable ☒ Bored ☐ Thermal: Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐
Thermal: Withdrawal ☐ Reinjection ☐

CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒

8" Diam. from 0 ft. to 349 ft. Gauge 250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used STAR

Size of perforations 3/8 in. by 1 1/2 in.

490 perforations from 295 ft. to 345 ft.

220 perforations from 194 ft. to 245 ft.

280 perforations from 140 ft. to 164 ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot Size Set from ft. to ft.

Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

a pump test made? ☒ Yes ☐ No If yes, by whom? DRILLER

d: 180 gal./min. with 69 ft. drawdown after 2 1/2 hrs.

" 275 " 139 " 7 "

Air test gal./min. with drill stem at ft. hrs.

Water test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used CEMENT

Well sealed from land surface to 18 ft.

Diameter of well bore to bottom of seal 12 in.

Diameter of well bore below seal 8 in.

Number of sacks of cement used in well seal 9 sacks

How was cement grout placed? TREMPLE

Was pump installed? No Type HP Depth ft.

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County CLACKAMAS Driller's well number
NE 1/4 NW 1/4 Section 4 T. 4S R. 1E W.M.
Tax Lot # Lot Blk Subdivision

Address at well location: SAME

(11) WATER LEVEL: Completed well.

Depth at which water was first found 38 ft.

Static level 58 ft. below land surface. Date OCT 23

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 8"

Depth drilled 351 ft. Depth of completed well 351 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOPSOIL	0	1	
CLAY BROWN	1	25	
SILTY CLAY BROWN	25	38	
SANDSTONE BROWN	38	49	
CLAY & CEMENT GRAVEL BROWN	49	89	
SILT BROWN	89	105	
SAND & SMALL GRAVEL	105	109	63'
CLAY BROWN	119	129	
CLAY GREY SILTY	129	154	
CEMENT GRAVEL	154	164	
CLAY GREEN	164	190	
CLAY BLUE	190	196	
GRAVEL & BLACK SAND	196	197	65'
CLAY LT BLUE	197	229	
SILT & BLACK SAND w/wood	229	244	65'
CLAY BLUE	244	291	
SILT - MAGENTA	291	295	
SAND BLACK	295	309	67
CLAY DK GREY	309	318	
SAND BLACK	318	347	67
CLAY DARK GREY	347	351	

Work started SEP 28 19 81 Completed OCT 22 19 81

Date well drilling machine moved off of well OCT 23 19 81

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Richard J. Beck Date OCT 23 19 81

(Drilling Machine Operator)

Drilling Machine Operator's License No. 1200

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Beck Well Drilling (Type or print)

(Person, firm or corporation)

Address 10300 SE CHAMPAGNE LN.

[Signed] Richard J. Beck (Water Well Contractor)

Contractor's License No. 743 Date OCT 23 19 81

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*12658-690