

WATER RESOURCES DEPARTMENT.
SALEM, OREGON 97310
within 30 days from the date
of well completion.

6-28

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

02356

CLAC

State Well No. 5-1E-500

State Permit No. 5-22-0

(1) OWNER:

Name Jim ZYRNOFF
Address 887 NW 13th
CANBY, OR.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☐

8" Diam. from 0 ft. to 170 ft. Gage 0.250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used STAR

Size of perforations 1 1/2 in. by 3/8 in.
510 perforations from 95 ft. to 129 ft.
60 perforations from 145 ft. to 152 ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom?

Yield: 180 gal./min. with 64 ft. drawdown after 7 hrs.
" " " "
" " " "

Ball test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 51 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used CEMENT
Well sealed from land surface to 18 ft.
Diameter of well bore to bottom of seal 12 in.
Diameter of well bore below seal 8 in.
Number of sacks of cement used in well seal 14 sacks
How was cement grout placed? PUMPED

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County CLACKAMAS Driller's well number
SW 1/4 SW 1/4 Section 95 T. 55 R. 140 E W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 11 ft.
Static level 52 ft. below land surface. Date 6/25/79
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 8

Depth drilled 190 ft. Depth of completed well 180 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL	0	3	
SILT BROWN	3	11	
SAND FINE BROWN	11	13	8
CLAY BROWN	13	20	
CLAY BLUE	20	51	
SILT BROWN	51	54	30
CLAY SILTY BROWN	54	67	
CEMENT Gravel BROWN	67	77	
CLAY BLUE	77	98	
CEMENT Gravel Grey	98	128	52
CLAY BLUE	128	154	
FINE SAND BLACK	154	158	52
CLAY BLUE	158	190	

Work started 11 Jun 1979 Completed 25 Jun 1979

Date well drilling machine moved off of well 25 Jun 1979

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Richard J. Beck Date 30 Jun 1979
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1200

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name (Person, firm or corporation) (Type or print)

Address J W Beck Well Drilling 11/22/79

[Signed] John W Beck Date 6-25-79
(Water Well Contractor)

Contractor's License No. 449 Date 6-25-79