

CLAC 2366

RECEIVED

WATER WELL REPORT

JUL 13 1959

STATE OF OREGON

State Well No. 51-5R11

State Permit No. G-1351

STATE ENGINEER

OBSERVATION WELL

File Original and
First Copy with the
STATE ENGINEER,
SALEM, OREGON

(1) OWNER:

Name H. D. ROGERS

Address R/T HUBBARD OPE

(2) LOCATION OF WELL:

Permit # G/1351

County Clatsop Owner's number, if any—

S.E. 1/4 Corner Section 5 T. 5. S. R. 1. E. W.M.

Bearing and distance from section or subdivision corner

Well is 1055' from N.W. from Section Corner

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level STEETLER

Was a pump test made? ☒ Yes ☐ No If yes, by whom? SUPPLY

Yield: 250 gal./min. with 50 ft. drawdown after 2 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 56° Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well 10" inches.

Depth drilled 139' ft. Depth of completed well 139' ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
TOPSOIL	2	2
CLAY YELLOW COLOR	22	24
CLAY BLUE SANDY	11	35
CLAY BLUE - STICKY	6	41
CLAY BROWN - FIRM	30	71
SANDSTONE - GREEN	6	77
SAND - FINE GRAIN	11'6"	88'6"
SHALE BLUE COLOR	28	116'6"
SHALE BROWN	66	123
SHALE GRAY	16	139

Work started 6-17-59 Completed 6-20-59

(13) PUMP:

Manufacturer's Name Western Pump Co. San Jose Calif.

Type: Turbine H.P. 15

Well Driller's Statement:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME J. A. SNEED & SONS

Address 2505 BROOKS ST SALEM

Driller's well number

[Signed] J. A. Sneed

(Well Driller)

License No. 6 Date 6-20-59

(3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 11.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐ Rotary ☐ Driven ☐
ation ☒ Test Well ☐ Other ☐ Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒

" Diam. from 139' ft. to 24" ft. Gage

" Diam. from ft. to ft. Gage

" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used MILLS

SIZE of perforations 3/8 in. by 2 1/2 in.

296 perforations from 67 ft. to 126 ft.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

(8) SCREENS:

Well screen installed ☐ Yes ☒ No

Manufacturer's Name

Model No.

Slot size Set from ft. to ft.

Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well gravel packed? ☒ Yes ☐ No Size of gravel: 2"

Gravel placed from 28 ft. to 90 ft.

Was a surface seal provided? ☒ Yes ☐ No To what depth? 6' +

Material used in seal—PUMP COVERED

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? Depth of strata

Method of sealing strata off

(10) WATER LEVELS:

Static level 7 ft. below land surface Date 6-20-59

Artesian pressure lbs. per square inch Date

Log Accepted by: A. D. ROGERS

[Signed] A. D. ROGERS Date 6-20-59

(Owner)