

The original and first copy
of this report and the
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No.

State Permit No.

WATER RESOURCES DEPT.

(1) OWNER: SALEM, OREGON

Name MALOFEE KRIVOSHEIN

Address Rt. 2, Box 106 C

Woodburn, Oregon 97071

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

8" Diam. from +1 ft. to 145 ft. Gage 250

" Diam. from ft. to ft. Gage

" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used MILLS KNIFE

Size of perforations 1 in. by 4 in.

48 perforations from 73 ft. to 79 ft.

perforations from ft. to ft.

perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static levelWas a pump test made? ☐ Yes ☒ No If yes, by whom?

Well: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 52 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used CEMENT

Well sealed from land surface to 18 ft.

Diameter of well bore to bottom of seal 12 in.

Diameter of well bore below seal 8 in.

Number of sacks of cement used in well seal 8 sacks

Number of sacks of bentonite used in well seal sacks

Brand name of bentonite

Number of pounds of bentonite per 100 gallons

of water lbs./100 gals.

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number 77-9

1/4 1/4 Section 8 T. 5S R. 1E W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 52 ft.

Static level 30 ft. below land surface. Date 5-10-77

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 8

Depth drilled 150 ft. Depth of completed well 150 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL	0	1	
BROWN CLAY	1	24	
BROWN CLAY & SAND	24	33	
BLUE CLAY	33	52	
BROWN SAND	52	56	30
BROWN RED CLAY & SAND	56	63	
BROWN SAND & FINE GRAVEL	63	70	
BROWN SAND & GRAVEL	70	79	25
BROWN CLAY	79	83	
GRAY/BLUE CLAY	83	87	
DARK GRAY CLAY	87	102	
LT. GRAY CLAY W/GRAVEL	102	122	
BLUE CLAY	122	135	
DARK BLUE CLAY & COARSE	135		
BLACK SAND		150	60

Work started 5-4 19 77 Completed 5-25 19 77

Date well drilling machine moved off of well 5-26 19 77

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Thomas D. Flores Date 6-11, 1977
(Drilling Machine Operator)

Drilling Machine Operator's License No. 978

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name FLORES WELL DRILLING
(Person, firm or corporation) (Type or print)

Address 12143 RIVER RD. N.E., GERVAIS 97026

[Signed] Thomas D. Flores
(Water Well Contractor)

Contractor's License No. 590 Date 6-11, 1977