

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97301 within 30 days from the date of well completion.

CLAC 2425

WATER WELL REPORT

STATE OF OREGON

(Please type or print) (Do not write above this line)

RECEIVED
SEP 25 1970
STATE ENGINEER
SALEM, OREGON

02425

CLAC

State Well No.

State Permit No.

5/1-9ca

(1) OWNER:

Name Burner Brothers
Address Rt 2 Box 165 Canby, Ore 97013

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☐
" Diam. from 12 ft. to 32 1/2 ft. Gage 250
" Diam. from 12 ft. to 96 1/2 ft. Gage 250
" Diam. from _____ ft. to _____ ft. Gage _____

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.
Type of perforator used touch
Size of perforations 3/8 in. by 6 in.
1200 perforations from 206 ft. to 306 ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WATER LEVEL: Completed well.

Static level 48 ft. below land surface Date 6-13-70
Artesian pressure _____ lbs. per square inch Date _____

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☒ Yes ☐ No If yes, by whom? driller
Yield: 1610 gal./min. with 202 ft. drawdown after 10 hrs.
745 " 118 " 10 1/2"
530 " 105 " 11"
Bailer test _____ gal./min. with _____ ft. drawdown after _____ hrs.
Artesian flow _____ g.p.m. Date _____
Temperature of water 54 Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used cement 13 1/2 yds
Depth of seal 97 ft.
Diameter of well bore to bottom of seal 36 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth _____
Was a drive shoe used? ☐ Yes ☒ No
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? ☒ Yes ☐ No Size of gravel: 3/4-3/8
Gravel placed from 97 ft. to 320 ft.

(11) LOCATION OF WELL:

County Clackamas Driller's well number 7005
1/4 1/4 Section 9 T. 55 R. 1E W.M.
Bearing and distance from section or subdivision corner _____

(12) WELL LOG:

Diameter of well below casing 0
Depth drilled 324 ft. Depth of completed well 314 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
<u>see sheet attached</u>			
<u>* all 12" casing below 150' perforated</u>			
<u>are 330 well</u>			
<u>6" diameter from 12 ft to 27 1/2" 250</u>			
<u>6" is domestic water 18" 250</u>			
<u>Perforations 3/8 x 2" on 6" casing</u>			
<u>360 perforations from 213 ft to 233 ft</u>			
<u>120 " 247 257"</u>			
<u>180 " 257 267"</u>			

Work started 4-15 19 70 Completed 8-25 19 70

Date well drilling machine moved off of well 8-25 19 70

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Edgar J. Mullen Date 9-23, 19 70
(Drilling Machine Operator)

Drilling Machine Operator's License No. 581

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Milo Schneider Equipment Co.
(Person, firm or corporation) (Type or print)

Address Stav Rt, Box 97 St. Paul, Ore

[Signed] Milo Schneider
(Water Well Contractor)

Contractor's License No. 387 Date 9-23, 19 70

8-25-70

Bronec Brothers

Well Log

Material	From	To
top soil	0	4
brown clay	4	14
blue clay	14	28
brown soft clay	28	40
sandy red pea gravel	40	45
brown shale	45	47
brown clay	47	50
brown sand & 2" gravel	50	52
brown clay	52	54
brown sand & pea gravel	54	61
brown clay	61	63
brown sand & gravel 2"	63	77
brown sandy clay	77	81
cemented sand	81	82
brown clay	82	85
blue clay	85	98
blue sandy clay	98	104
blue clay	104	122
cemented green clay	122	125
blue silty clay (wood 131-133)	125	134
blue clay	134	215
fine gray sand	215	233
brown clay	233	238
blue clay	238	261
gray sand	261	264
blue clay	264	272
blue silty clay	272	278
brown clay	278	287
blue clay	287	290
gray sand	290	298
brown clay	298	304
gray sand	304	308
blue clay	308	317
green clay	317	324

RECEIVED
 SEP 25 1970
 STATE ENGINEER
 SALEM, OREGON

7-30-70

Very well test
6 miles west of Multnomah
Started Pump - 7:00 AM

Brown Box

Box 2 Box 140
Condy Ore

6 miles west of Multnomah

Box 48 - 6-13-70

MIL SCHNEIDER EQUIPMENT CO.
STAR ROUTE, BOX 97
ST. PAUL, OREGON - PH. 613-2666

Discovery

Start off - 7:30 PM 153' 6"
7:35 " - 147' 10"
7:40 " - 139' 4"
7:45 " - 136' 10"
7:50 " - 133' 7"
7:55 PM - 131' 10"

RECEIVED
SEP 25 1970
STATE ENGINEER
SALMON, OREGON

9:30 PM 153' 8" - 500' from
9:00 PM 166' 10" - 745' from

4 PM →

1970