

CLAC
02479

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM 10, OREGON
within 30 days from the date
of well completion.

OCT 23 1962

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

SALEM, OREGON

State Well No. _____

State Permit No. _____

G3186

(1) OWNER:

Name Gilman Satrum
Address Rt. 3, Box 250
Molalla, Oregon

(2) LOCATION OF WELL:

County Clackamas Driller's well number 321
NW S $\frac{1}{4}$ SW $\frac{1}{4}$ Section 12 T. 5S R. 1E W.M.
Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandonment ☐
Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 97 ft. Gage 17.02
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Puddled Clay
Depth of seal 29 ft. Was a packer used? No
Diameter of well bore to bottom of seal 10 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth _____
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ Depth of strata _____
Method of sealing strata off _____

(10) WATER LEVELS:

Static level 48 ft. below land surface Date 10/19/62
Artesian pressure _____ lbs. per square inch Date _____

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield:	gal./min. with	ft. drawdown after	hrs.
"	"	"	"
"	"	"	"

Bailer test 55 gal./min. with 20 ft. drawdown after 1 hrs.

Artesian flow _____ g.p.m. Date _____

Temperature of water 52 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 6Depth drilled 130 ft. Depth of completed well 130 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Soil, brown	0	2
Clay, tan	2	12
Gravel, coarse, & clay	12	30
Gravel & clay	30	71
Clay, tan	71	74
Clay, pink to tan	74	80
Clay, brown	80	95
Clay, bluish grey	95	100
Clay, sandy, grey	100	102
Clay, sandy, brown	102	104
Sand, coarse, brown	104	115
Clay, brown	115	130

Work started 9/24 1962. Completed 10/19 1962Date well drilling machine moved off of well 10/20 1962

(13) PUMP:

Manufacturer's Name _____

Type: _____ H.P. _____

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME C. G. Westerberg
(Person, firm or corporation) (Type or print)

Address Rt. 1, Box 151, Mulino, OregonDrilling Machine Operator's License No. 86

[Signed] C. G. Westerberg
(Water Well Contractor)

Contractor's License No. 86 Date 10/22, 1962



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.oregon.gov/owrd

Application for Well ID Number

RECEIVED

DEC 14 2020

OWRD

Do not complete if the well already has a Well Identification Number.

I. OWNER INFORMATION

Current Owner Name (please print): Luis R Santos Morales & Miguel Vega
Mailing Address: 11208 S Hwy 211
City, State, Zip: Molalla, OR 97038
Mail Well ID to: ☒ SAME AS ABOVE ☐ In Care Of (C/O)
Name & Address: _____
City, State, Zip: _____

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 5 S (North / South) Range: 1 E (East / West) Section: 12 NW 1/4 of the SW 1/4
Tax Lot (usually last 3-5 numbers of Tax Map #): 1200 County Clackamas
GPS Coordinates: 45.1490629485; -122.6367143368
Street Address of Well, City: 11208 S Hwy 211 Molalla, OR 97038
If the property had a different street address in the past: _____

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Report, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Domestic, irrigation
Date Well Constructed (or property built): 10/19/1962 Total Well Depth: 130 Casing Diameter: 6
Owner at time the well was constructed (if known): Gilman Satrum Well Report # (if known): CLAC 2479
Other Information: _____

SUBMITTED BY (please print): Luis R Santos Morales
PHONE: 503-951-9384 EMAIL &/or FAX: Santos12911@gmail.com

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902.
Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

For Official Use Only by the Oregon Water Resources Department:

Received Date:
12-14-2020

Well Report Number:
CLAC 2479

Well Identification #:
L 140930