

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

RECEIVED

WATER WELL REPORT

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date of well completion

DEC 1 1966

STATE OF OREGON
(Please type or print)

CLAC

02527

State Well No.

5/1-16 E

G-3805

State Permit No.

(1) OWNER:

SALEM, OREGON

Name Tom WATTS

Address RT 2 Box 157 AA
Canby Oregon

(2) LOCATION OF WELL:

County Clackamas Driller's well number 167
SW 1/4 SW 1/4 Section 16 T. 57 R. 1E W.M.
Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

(5) TYPE OF WELL:

Domestic ☒ Industrial ☐ Municipal ☐ Rotary ☐ Driven ☐
Irrigation ☒ Test Well ☐ Other ☐ Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☐

8" Diam. from 0 ft. to 150 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Reddell Clay
Depth of seal 30 ft. Was a packer used? Yes
Diameter of well bore to bottom of seal 12 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 39' ft. below land surface Date Nov 28/66
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☐ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test 65 gal./min. with 24 ft. drawdown after 3/4 hrs.

Artesian flow g.p.m. Date

Temperature of water Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 8

Depth drilled 163 ft. Depth of completed well 160 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Topsoil	0	2
Clay Light Brown Sandy	2	55
Sand Fine Clay Brown	55	66
about 10 GPM at 65'		
Clay Blue Sandy	66	105
Clay Light Tan	105	125
Clay Light Tan Sand Fine	125	130
Clay Tan Very gummy	130	145
Clay Blue	145	152
Sand Coarse to Fine Clay Blue	152	163

Work started Nov 22 19 66 Completed Nov 28 19 66

Date well drilling machine moved off of well Nov 28 19 66

(13) PUMP:

Manufacturer's Name

Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Tollison Drilling Co (Type or print)

Address RT 1 Box 268 Mulino Oregon

Drilling Machine Operator's License No. 174

[Signed] Richard R. Tollison (Water Well Contractor)

Contractor's License No. 264 Date Nov 29 19 66