

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

Do not write above this line

RECEIVED

JUL 25 1973

STATE ENGINEER

SALEM OREGON

State Well No.

55/1E-20

Permit No.

6-6551

(1) OWNER:

Name ZOTIK Kosh Karosf
Address Rt 1 Box 260
Woodburn Ore.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
8" Diam. from 0 ft. to 100 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used STAR
Size of perforations 3/8 in. by 1 1/2 in.
50 perforations from 49 ft. to 56 ft.
100 perforations from 70 ft. to 90 ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? By Driller
Yield: 60 gal./min. with 54 ft. drawdown after 4 hrs.
" " " "
" " " "
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water 53° Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used RAW CEMENT
Well sealed from land surface to 30 ft.
Diameter of well bore to bottom of seal 12 in.
Diameter of well bore below seal 8 in.
Number of sacks of cement used in well seal 4 sacks
Number of sacks of bentonite used in well seal sacks
Brand name of bentonite
Number of pounds of bentonite per 100 gallons
of water lbs./100 gals.
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County CLACKAMAS Driller's well number
NW 1/4 NW 1/4 Section 20 T. 53 R. 1 E W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 49 ft.
Static level 26 ft. below land surface. Date 7-4-73
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 8"

Depth drilled 112 ft. Depth of completed well 112 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL	0	1	
BROWN CLAY	1	12	
BROWN SANDY CLAY	12	22	
BLUE CLAY	22	35	
BROWN SANDY CLAY	35	45	
CEMENT GRAVEL	45	56	
BROWN CLAY	56	70	
BROWN SANDY CLAY	70	80	
GRAYISH SANDY CLAY	80	90	
BROWN CLAY	90	105	
BLUE CLAY	105	112	

Work started 6-25 19 73 Completed 7-5 19 73
Date well drilling machine moved off of well 7-5 19 73

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Richard L. Wright Date 7-5, 19 73
(Drilling Machine Operator)

Drilling Machine Operator's License No. 762

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name John Beck well Drilling
(Person, firm or corporation) (Type or print)
Address 110 S. K. 12th Ave. Corvallis Ore.
[Signed] John W. Beck 77019
(Water Well Contractor)

Contractor's License No. 449 Date 7-5, 19 73