

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 973
within 30 days from the date
of well completion.

STATE OF OREGON

Please type or print) ()
Do not write above this line)

CLAC
02692

State Well No. 5712-29db

State Permit No.

STATE ENGINEER
SALEM, OREGON

Name Oscar Satrum
Address Route 2, Box 240, Woodbrun, Ore

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

Threaded ☐ Welded ☒

12 " Diam. from _____ ft. to _____ ft. Gage # 250
" Diam. from 0 ft. to 75 ft. Gage # 250
" Diam. from 93 ft. to 115 ft. Gage # 111

188-208-250
Perforated? ☒ Yes ☐ No.

Type of perforator used		Size of perforations		in by	
140	perforations from	240	ft. to	260	ft.
36	perforations from	128	ft. to	131	ft.
100	perforations from	230	ft. to	250	ft.
	perforations from		ft. to		ft.

Well screen installed? ☒ Yes ☐ No

Manufacturer's Name		Johnson	
Type	Irrigator	Model No.	100
Diam.	12	Slot size	100
Set from	145	ft. to	208
Diam.	12	Slot size	100
Set from	145	ft. to	208

Static level 37 ft. below land surface Date 10/28
 an pressure lbs. per square inch Date

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom?

Id: 100 gal./min. with 176 ft. drawdown after 7 hrs.

" " "

" " "

Bailer test	gal./min. with	ft. drawdown after	hrs.
Artesian flow	g.p.m. Date		
Temperature of water	Was a chemical analysis made? ☐ Yes ☒ No		

Well seal—Material used Cement & Bentonite
Depth of seal 20 ft.
Diameter of well bore to bottom of seal 28 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth _____
Was a drive shoe used? ☐ Yes ☒ No
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? ☒ Yes ☐ No Size of gravel: 3/8-I/4
Gravel placed from _____ ft. to 250 ft.

County Clackamas		Driller's well number		
$\frac{1}{4}$	$\frac{1}{4}$ Section	T.	R.	W.M.

Bearing and distance from section or subdivision corner
2150' W & 1675' N. of S.E. Cor Sec 29
T 5 S R 1 E.

Diameter of well below casing

Depth drilled 250 ft. Depth of completed well 250 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

[illegible]

Work started	10/7/68	Completed	10/28/68
Date well drilling machine moved off of well	10/28		1968

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] C. E. Madeli Date 11/18, 1968
(Drilling Machine Operator)

Drilling Machine Operator's License No. 84

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME R. Stadeli & Sons
(Person, firm or corporation) (Type or print)

Address Silverton, Oreg

[Signed] Paul G. Stedeli
(Water Well Contractor)

Contractor's License No. 296 Date 11/18 1968