

# NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON within 30 days from the date of well completion.

SEP 23 1963

## WATER WELL REPORT

STATE OF OREGON (Please type or print)

State Well No. 51-33R

State Permit No. 62447

### (1) OWNER:

Name L.E. PAQUIN  
Address RTE 2 Box 2234  
WOODBURN, OREGON

### (2) LOCATION OF WELL:

County CLACKAMAS Driller's well number  
SE 1/4 SE 1/4 Section 33 T. 75S R. 1E W.M.  
Bearing and distance from section or subdivision corner  
N 63° 17' W - 1264' from  
SE corner Section 33

### (3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐  
Abandonment, describe material and procedure in Item 12.

### (4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐  
Irrigation ☒ Test Well ☐ Other ☐

### (5) TYPE OF WELL:

Rotary ☐ Driven ☐  
Cable ☒ Jetted ☐  
Dug ☐ Bored ☐

### (6) CASING INSTALLED:

Threaded ☐ Welded ☒  
8" Diam. from 1' above ft. to 112'-08" ft. Gage 250  
" Diam. from ..... ft. to ..... ft. Gage .....  
" Diam. from ..... ft. to ..... ft. Gage .....

### (7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

| Size of perforations                     | in. by | in. |
|------------------------------------------|--------|-----|
| perforations from ..... ft. to ..... ft. |        |     |
| perforations from ..... ft. to ..... ft. |        |     |
| perforations from ..... ft. to ..... ft. |        |     |
| perforations from ..... ft. to ..... ft. |        |     |
| perforations from ..... ft. to ..... ft. |        |     |

### (8) SCREENS:

Well screen installed ☐ Yes ☒ No

Manufacturer's Name ..... Model No. ....  
Diam. .... Slot size ..... Set from ..... ft. to ..... ft.  
Diam. .... Slot size ..... Set from ..... ft. to ..... ft.

### (9) CONSTRUCTION:

Well seal—Material used in seal Concrete 5 to 1 cement  
Depth of seal 2.8 ft. Was a packer used? no clay  
Diameter of well bore to bottom of seal 19 in.  
Were any loose strata cemented off? ☐ Yes ☒ No Depth .....  
Was a drive shoe used? ☒ Yes ☐ No  
Was well gravel packed? ☐ Yes ☒ No Size of gravel: .....  
Gravel placed from ..... ft. to ..... ft.  
Did any strata contain unusable water? ☐ Yes ☒ No  
Type of water? ..... Depth of strata .....  
Method of sealing strata off .....

### (10) WATER LEVELS: FLOW VARIES FROM 10 X 5 GPM

Static level Flowing 4 ft. below land surface Date 8-6-63  
Artesian pressure ? lbs. per square inch Date .....

### (11) WELL TESTS:

Drawdown is amount water level is lowered below static level  
Was a pump test made? ☒ Yes ☐ No If yes, by whom? DRILLERS

Yield: 60 gal./min. with 114 ft. drawdown after 7 hrs.

Bailer test 54 gal./min. with 40 ft. drawdown after 1 hr.

Artesian flow FROM 10 X 5 g.p.m. Date 8-6-63

Temperature of water ? Was a chemical analysis made? ☐ Yes ☒ No

### (12) WELL LOG:

Diameter of well below casing 7 1/8"  
Depth drilled 124 1/2 ft. Depth of completed well 124 1/2 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

| MATERIAL                    | FROM | TO      |
|-----------------------------|------|---------|
| TOP-SOIL-BROWN              | 0    | 2       |
| CLAY-BROWN                  | 2    | 15      |
| CLAY-GREY + STICKY          | 15   | 38      |
| CAVING AROUND 20 FT.        |      |         |
| CLAY-BRICK RED              | 38   | 55      |
| CLAY-SANDY-LIGHT GREY       | 55   | 83      |
| CLAY-LIGHT-BROWN-SANDY-WITH |      |         |
| SCATTERED-MED. BLACK-GRAVEL | 83   | 101     |
| CLAY-SANDY-BLUE-FIRM        | 101  | 108     |
| ROCK-BASALT-BLUE-SOFT       | 108  | 115     |
| ROCK-BASALT-BLUE-MED.HD.    | 115  | 121     |
| WATER CAME IN AT 121 FT.    |      |         |
| ROCK-BASALT-BLUE-HARD       | 121  | 124 1/2 |

Work started MAY 30 1963 Completed AUG. 6 1963  
Date well drilling machine moved off of well AUG. 6 1963

### (13) PUMP:

Manufacturer's Name UNIVERSAL  
Type: SUBMERSIBLE H.P. 5

### Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME R. STADELI & SONS  
(Person, firm or corporation) (Type or print)

Address RTE 3 Box 169, SILVERTON, OREGON

Drilling Machine Operator's License No. 16

[Signed] Paul R. Stadel  
(Water Well Contractor)

Contractor's License No. 296 Date Aug 10, 1964