

#16
STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

OCT 26 1990
WATER RESOURCES DEPT.
OREGON

(START CARD) # 24862

(1) OWNER:

Name Robert W. Kaiser

Address 2390 SW Advance Rd.

City West Linn, Or

State OR

Zip 97068

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable

☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☒ Irrigation

☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes ☐ No ☒ Depth of Completed Well 497 ft.

Explosives used Yes ☐ No ☒ Type Amount

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
12	0	189	Cement	0	189	62 sacks
			Bentonite			4 sacks
8	189	497				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E

☐ Other

Backfill placed from ft. to ft. Material

Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8	+1	189	.250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

☐ Perforations Method

☐ Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
400		497	1 hr.

Temperature of water 54° Depth Artesian Flow Found

Was a water analysis done? ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County Clackamas Latitude Longitude

Township 3S N or S, Range 1E E or W, WM.

Section 16 NW 1/4 NW 1/4

Tax Lot Lot Block Subdivision

Street Address of Well (or nearest address) 2390 SW Advance Rd.

West Linn, OR 97068

(10) STATIC WATER LEVEL:

128 ft. below land surface. Date 10-16-90

Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 252

From	To	Estimated Flow Rate	SWL
201	265	30 gpm	128
383	394	60 gpm	128
415	424	60 gpm	128
444	497	250 gpm	128

(12) WELL LOG:

Ground elevation

Material	From	To	SWL
Top soil	0	1	
Clay hard brown	1	4	
Clay brown soft	4	26	
Decompose rock red	26	32	
Clay grey w/ gravels	32	65	
Clay brown	65	130	
Clay crumbly soft	130	158	
Clay grey crumbly	158	175	
Basalt grey weathered	175	182	
Basalt grey harder	182	201	
Basalt weathered	201	265	
Basalt grey medium hard	265	307	
Basalt weathered	307	346	
Basalt red hard (medium)	346	356	
Basalt weathered	356	374	
Basalt grey hard	374	383	
Basalt red pourous	383	394	
Basalt weathered hard	394	408	
Basalt grey slightly weathered	408	415	
Basalt brown pourous	415	424	
Basalt grey hard	424	444	
Basalt brown pourous	444	460	
Continued on next page...			

Date started 10-10-90 Completed 10-16-90

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed *Byron B. Stutts* WWC Number 1358 Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed *[Signature]* WWC Number 723 Date

