

OCT - 5 1988

Skyles Drilling Inc.

16200 S. Ave.

FEB 14, 1989

CLACKAMAS

STATE OF OREGON
WATER RESOURCES DEPT.
WATER WELL REPORT
(as required by ORS 537.765)

Oregon City, Oregon 97045
656-2683

WATER RESOURCES DEPT.
SALE (START CARD) # 5450

00314
CLAC

(1) OWNER:

Well Number: 02

Name Blair & Debbie Anderson
Address 25090 S.E. Henningson Road
City Gresham State Oregon Zip 97080

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable

☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation

☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes No Depth of Completed Well 185 ft.

Explosives used ☐ Yes ☒ No Type Amount

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
10"	0	18	Gran. Bent.	0	18'	12 sacks
6"	18	185				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other Granular bentonite placed dry

Backfill placed from ft. to ft. Material

Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6"	+1	148	.250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:	4"	125	185	160#	☐	☒	☒	☐
					☐	☐	☐	☐

Final location of shoe(s) 148'

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Air Rotary & Saw

☐ Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
114	144	1/8"	396			☒	☐
167	184	3/16"	80			☐	☒
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing
☐ Artesian

Yield gal/min	Drawdown	Drill stem at	Time
50		185'	1 hr.
35		140'	1/2 hr.

Temperature of water 52° Depth Artesian Flow Found

Was a water analysis done? ☒ Yes By whom Driller

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County Clackamas Latitude Longitude

Township 1 So. Nor S, Range 3 East E or W, WM.

Section 35 N.E. 1/4 N.W. 1/4

Tax Lot Lot Block Subdivision

Street Address of Well (or nearest address) 25090 S.E. Henningson
Gresham, Oregon 97080

(10) STATIC WATER LEVEL:

110 ft. below land surface.

Date 9-15-88

Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 110'

From	To	Estimated Flow Rate	SWL
110'	144'	5 gpm	
178'	185'	50 gpm	110'

(12) WELL LOG:

Ground elevation

Material	From	To	SWL
Clay brown	0	42	
Lava red soft	42	80	
Gravel & Clay	80	94	
Clay yellow	94	110	
Gravel med., partially cemented	110	144	
Gravel med. to large cemented	144	178	
Gravel medium (water bearing)	178	185	110'
Gravel medium cemented	185	189	

Date started 9-14-88 Completed 9-15-88

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

WWC Number

Signed Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 553

Signed Martin D. Super Date Sep. 16, 1988

CLAC 314

WELL IDENTIFICATION APPLICATION FORM

DONNA M. STARITA

BUYER/CURRENT WELL OWNER:Name: KEITH & DEBORAH FLEWELLINGMailing Address: P.O. Box 1582City: GRESHAM State: OR Zip: 97030 Phone: 503 788-9714**WELL LOCATION:**County: Clackamas Township: 1 N or (S) Range: 3 (E) or WSection: 35 1/4 NW 1/4 Owner's Well Number: _____Tax Lot Number: 00101 Street Address of Well (if different from above): 25090SE HENNINGSEN ROAD, GRESHAM, OR 97080SEND TAG TO NEW OWNER AT ABOVE ADDRESS**WELL INFORMATION: (do not complete remainder of application if well log is available)**Start Card Number: 5450 Approx. Construction Date: Sept 88Well Constructor: Blair & Debbie AndersonName of Owner at Time of Construction: Skyles Drilling, Inc.Well Depth (in feet): ? Static Water Level (in feet): 110Diameter of Exposed Well Casing (in inches): 6"Does this well have a formal water right associated with it? Yes: ☒ No: _____If Yes: Application #: G-13471 Permit #: G-12030 Certificate #: _____

Please Return Completed Form to:

Lisa Juul
Well Identification Program
Oregon Water Resources Department
158 12th Street NE
Salem, OR 97310
503-378-8130

For Official Use Only:

Well Tag No. 35801

N:\wellid.app

RETURN FAX: 669-9384

faxed copy
of WOI#
7-26-99
J. Juul