

WATER WELL REPORT
STATE OF OREGON

RECEIVED

FEB 2 1983

State Well No.

25/1E-2966

State Permit No.

CLAC

03550

WATER RESOURCES DEPT.
SALEM, OREGON

(1) OWNER:

Name Ben Label
Address 2990 Portland Road
City Sualatin State Ore.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☐ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☐ Test Well ☐ Other ☐
Cable ☒ Bored ☐ Thermal: Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☐
6" Diam. from +1 ft. to 224 ft. Gauge 250
" Diam. from _____ ft. to _____ ft. Gauge _____

LINER INSTALLED:

4" Diam. from 210 ft. to 250 ft. Gauge 160#

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No
Type of perforator used SMU
Size of perforations 7 in. by 1/8" in.
66 perforations from 210 ft. to 250 ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot Size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot Size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☐ Yes ☒ No If yes, by whom?
gal./min. with _____ ft. drawdown after _____ hrs.
Air test _____ gal./min. with drill stem at _____ ft. _____ hrs.
Bailer test 13 gal./min. with 82 ft. drawdown after 1 hrs.
Artesian flow _____ g.p.m.
Temperature of water _____ Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒
Well seal—Material used Cement
Well sealed from land surface to 30 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 25 sacks
How was cement grout placed? grouted

Was pump installed? no Type _____ HP _____ Depth _____ ft.
Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of Water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number _____
NW 1/4 NW 1/4 Section 29 T. 25 R. 1E W.M.
Tax Lot # 500 Lot _____ Blk _____ Subdivision _____
Address at well location: _____

(11) WATER LEVEL: Completed well.

Depth at which water was first found 230 ft.
Static level 98 ft. below land surface, Date 1-9-83
Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 6 in.
Depth drilled 250 ft. Depth of completed well 250 ft.
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Brown Sand	0	43	
Gray Clay	43	121	
Blue Clay	121	162	
Gray Clay	162	210	
Gray Clay + Sand	210	240	
Red Brown Clay + Sand	240	250	

Work started 12/28 1982 Completed 1/10 1983
Date well drilling machine moved off of well 1/17/83 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.
[Signed] Donald L. Russell Date 1-17, 1983
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1050

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name CRIS-WEIL Drilling Co. (Type or print)
(Person, firm or corporation)

Address 600 E. Rosemont Rd. Gresham, OR

[Signed] Donald L. Russell (Water Well Contractor)

Contractor's License No. 647 Date Jun 17, 1983

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*12658-690