

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

RECEIVED
STATE ENGINEER
SALEM OREGON
 MAY 15 1969

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

Do not write above this line

CLAC

04020

State Well No. 2/2-9cc

State Permit No.

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date of well completion

(1) OWNER:

Name Johnson Mobile Court
 Address 8000 S. E. Root Road
Milwaukie, Ore. 97222

(2) TYPE OF WORK (check):

New Well Deepening Reconditioning Abandon

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Driven
 Cable Jetted
 Dug Bored

(4) PROPOSED USE (check):

Domestic Industrial Municipal
 Irrigation Test Well Other

CASING INSTALLED:

Threaded Welded

8" Diam. from 0 ft. to 158 ft. Gage .250

" Diam. from " ft. to " ft. Gage

" Diam. from " ft. to " ft. Gage

PERFORATIONS:

Perforated? Yes No

Type of perforator used Mills Knife

Size of perforations 1/2 in. by 2 in.

130 perforations from 125 ft. to 155 ft.

perforations from " ft. to " ft.

perforations from " ft. to " ft.

perforations from " ft. to " ft.

perforations from " ft. to " ft.

perforations from " ft. to " ft.

(7) SCREENS:

Well screen installed? Yes No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from " ft. to " ft.

Diam. Slot size Set from " ft. to " ft.

(8) WATER LEVEL: Completed well.

Static level 35 ft. below land surface Date 4/29

Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? Yes No If yes, by whom?

Yield: gal./min. with " ft. drawdown after " hrs.

" " " " " "

" " " " " "

Bailer test 70 gal./min. with 20 ft. drawdown after 2 hrs.

Artesian flow g.p.m. Date

Temperature of water 54 Was a chemical analysis made? Yes No

(10) CONSTRUCTION:

Well seal—Material used Bentonite & Drill Mud

Depth of seal 37' ft.

Diameter of well bore to bottom of seal 12" to 21" 10"-37" ft.

Were any loose strata cemented off? Yes No Depth

Was a drive shoe used? Yes No

Did any strata contain unusable water? Yes No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? Yes No Size of gravel:

Gravel placed from " ft. to " ft.

(11) LOCATION OF WELL:

County Clackamas Driller's well number 277-69
S.W 1/4 S.W. 1/4 Section 9 T. 2 S R. 2 E W.M.

Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing 8"

Depth drilled 160 ft. Depth of completed well 159 1/2 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Top Soil	0	1	
Gravel & Clay Conglomerate	1	3	
Clay, Brown	3	7	
Gravel & Clay Conglom.	7	17	
Sand & Gravel, loose	17	26	
Clay, Brown, Conglom.	26	37	
Gravel, loose Conglom.	37	60	
Gravel & Sand	60	66	
Gravel & Sand Conglom.	66	96	
Gravel, Cemented	96	100	
Gravel, Conglom.	100	108	
Gravel & Sand, loose	108	111	
Gravel, Cemented	111	127	
Gravel & Sand loose	127	136	37
Gravel, Cemented	136	150	
Gravel & Sand, loose	150	160	35

Work started 4/9 19 69 Completed 4/29 19 69

Date well drilling machine moved off of well 4/30 19 69

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Floyd Benson Date May 8, 1969
 (Drilling Machine Operator)

Drilling Machine Operator's License No. 69

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Steinman Bros.
 (Person, firm or corporation) (Type or print)

Address Milwaukie, Ore. 97222

[Signed] Robert E. McConnell
 (Water Well Contractor)

Contractor's License No. 1 Date May 8, 1969