

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

RECEIVED
MAR 25 1966

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

CLACKAMAS

00428

State Well No. 1/3-25

State Permit No. G3445

STATE ENGINEER

(1) OWNER:

SALEM OREGON

Name Ken Stone

Address Freshman, Oreg.

(2) LOCATION OF WELL:

County Clackamas Driller's well number
1/4 1/4 Section 25 T. 15 R. 3E W.M.

Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
In abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒

8" Diam. from 0 ft. to 232 ft. Gage 277

" Diam. from ft. to ft. Gage

" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☐ Yes ☐ No

Type of perforator used Mills Knife

Size of perforations 1/4 in. by 3 in.

4 per ft. perforations from 123 ft. to 230 ft.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

cemented below 60'

Well seal—Material used in seal

Depth of seal below 60 ft. Was a packer used?

Diameter of well bore to bottom of seal 10 in.

Were any loose strata cemented off? ☐ Yes ☐ No DepthWas a drive shoe used? ☒ Yes ☐ NoWas well gravel packed? ☐ Yes ☐ No Size of gravel:

Gravel placed from ft. to ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

(10) WATER LEVELS:

Static level 64 ft. below land surface Date March 1964

Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is
lowered below static levelWas a pump test made? ☒ Yes ☐ No If yes, by whom? driller

Yield: 200 gal./min. with 14 ft. drawdown after 2 hrs.

" 275 " 26 " 2 "

" 380 " 34 " 2 "

Bailer test 40 gal./min. with 1 ft. drawdown after 2 hrs.

Artesian flow g.p.m. Date

Temperature of water Was a chemical analysis made? ☐ Yes ☐ No

(12) WELL LOG:

Diameter of well below casing to bottom,

Depth drilled 232 ft. Depth of completed well 232 ft.

Formation: Describe by color, character, size of material and structure, and
show thickness of aquifers and the kind and nature of the material in each
stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
0-2 Top soil	0	2
Yellow clay	2	35
Cement gravel	35	95
Loosely cemented	95	105
water bearing static 42'		
Loose sand gravel	105	125
no water,		
loosely cemented gravel	125	155
and sand -		
loosely cemented gravel	155	180
Loose gravel & sand,	180	232

set 10" casing to 60'

set 8" casing at 85'

Work started Jan 27 1964 Completed March 19 1964

Date well drilling machine moved off of well March 12 1964

(13) PUMP:

Manufacturer's Name

Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

NAME A. O. Olsen

(Person, firm or corporation)

(Type or print)

Address 18211 SE Powell Freshman

Drilling Machine Operator's License No. 215

[Signed] A. O. Olsen

(Water Well Contractor)

Contractor's License No. 282 Date March 30 1964

(USE ADDITIONAL SHEETS IF NECESSARY)