

MAY 09 1990

CLAC 48

STATE OF OREGON WATER WELL REPORT (as required by ORS 537.765)

WATER RESOURCES DEPT. SALEM, OREGON

CLAC 048 45/1E/2766 (START CARD) # 15333

(1) OWNER: Name Shirley Kimlinger, Address 2846 Lorencita, City Santa Maria, State CA, Zip 93455

(2) TYPE OF WORK: [X] New Well, [] Deepen, [] Recondition, [] Abandon

(3) DRILL METHOD: [] Rotary Air, [] Rotary Mud, [X] Cable, [] Other

(4) PROPOSED USE: [] Domestic, [] Community, [] Industrial, [X] Irrigation, [] Thermal, [] Injection, [] Other

(5) BORE HOLE CONSTRUCTION: Special Construction approval Yes No, Depth of Completed Well 360 ft., Explosives used [] [X] Type Amount

Table with columns: HOLE Diameter, From, To, SEAL Material, From, To, Amount sacks or pounds. Row 1: 16", 0, 25, cement, 0, 25, 37 sacks. Row 2: 12", 25, 360.

How was seal placed: Method [] A [] B [X] C [] D [] E, Backfill placed from ft. to ft., Material, Gravel placed from 266 ft. to 360 ft., Size of gravel pea 3/8

(6) CASING/LINER: Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Casing: 12", +2, 288'5", .250 [X] [] [X] []. Liner: [] [] [] [].

(7) PERFORATIONS/SCREENS: [] Perforations Method, [X] Screens Type Material stainless st

Table with columns: From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner. Rows: 266' 290' 4", 290' 4" 298' 4", 298' 4" 324' 6", 324' 6" 336' 6", 336' 6" 360' 4".

(8) WELL TESTS: Minimum testing time is 1 hour. [] Pump, [] Bailer, [X] Air, [] Flowing Artesian. Yield gal/min, Drawdown, Drill stem at, Time.

Temperature of water 54°, Depth Artesian Flow Found, Was a water analysis done? [] Yes By whom, Did any strata contain water not suitable for intended use? [] Too little, [] Salty [] Muddy [] Odor [] Colored [] Other, Depth of strata:

(9) LOCATION OF WELL by legal description: County Clackamas, Latitude, Longitude, Township 4S, N or S, Range 1E, E or W, WM, Section 27, NW 1/4, NW 1/4, Tax Lot 00-400, Lot, Block, Subdivision, Street Address of Well (or nearest address) Canby - Marquam RD. S of Gribble Rd. Canby, OR

(10) STATIC WATER LEVEL: 23 ft. below land surface, Date 4/23/90, Artesian pressure lb. per square inch, Date

(11) WATER BEARING ZONES: Table with columns: From, To, Estimated Flow Rate, SWL. Row 1: 144, 154, 300gpm, 23. Row 2: 291, 301, 800 gpm, 23. Row 3: 326, 338, 800 gpm, 23.

(12) WELL LOG: Table with columns: Material, From, To, SWL. Rows: Clay brown (0-12), Clay sandy brown (12-16), Clay brown (16-19), Clay grey (19-36), Clay grey, gravel (36-61), Clay grey (61-86), Clay grey sandy (86-101), Clay grey gravel (101-104), Clay grey (104-112), Clay grey, gravel (112-123), Gravel cemented (123-125), Clay grey sticky (125-143), Gravel & clay (143-144), Sand coarse black (144-154, 23'), Clay grey sticky (154-258), Clay grey, gravel (258-277), Clay sandy grey (277-279), Clay, gravel (279-291), Sand black (291-301, 23'), Clay sticky (301-323), Clay sandy grey (323-326), Sand black (326-338, 23'), Clay grey (338-360).

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief. WWC Number, Signed, Date

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief. WWC Number 783, Signed Ivan Brown, Date 5/6/90



Oregon Water Resources Department
 725 Summer Street NE, Suite A
 Salem Oregon 97301
 (503) 986-0900
 www.wrd.state.or.us

Application for Well ID Number

RECEIVED

JUL 18 2016

WATER RESOURCES DEPT
 SALEM, OREGON

Do not complete if the well already has a Well Identification Number.

I. OWNER INFORMATION

Current Owner Name (please print): Shirley B. Kimlinger, TTEE Raymond J. & Shirley B. Kimlinger Rev. Living Trust UDT 12/31/1997; and family below:

Mailing Address: 2807 Lorencita Dr.

City, State, Zip: Santa Maria, CA 93455

Mail Well ID Tag to: SAME AS ABOVE In Care Of (C/O)

Name & Address: Owner information continued: James R. Kimlinger, TTEE Kimlinger Fam. Rev. Trust UDT 07/07/2006; William R. Kimlinger, TTEE

City, State, Zip: William R. & Melinda M. Kimlinger Joint Rev. Living Trust, UDT 5/13/2010; Susan Marie Kimlinger Doolittle; Mary Jane Kimlinger Davis

MAIL TAG TO: % BILL LEDER, HALLMARK PROPERTIES 735 GLATT CIR WOODBURN OR 97071

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 4S (North / South) Range: 1E (East / West) Section: 27 1/4 of the 1/4

Tax Lot (usually last 3-5 numbers of Tax Map #): 00-400 County Clackamas

GPS Coordinates:

Street Address of Well, City: Canby - Marquam Rd., South of Gribble Rd. (cross street); at NE corner of Gribble Barn

If the property had a different street address in the past:

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Log, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Irrigation

Date Well Constructed (or property built): Total Well Depth: 360' Casing Diameter: 12"

Owner at time the well was constructed (if known): Shirley Kimlinger or Don Bowers Well Log # (if known): Clac 048

Other Information:

SUBMITTED BY (please print): James & Kendra Kimlinger, TTEEs of the Kimlinger Family Revocable Trust udt 07-07-2006

PHONE: 805-929-5775

EMAIL &/or FAX: kkimlinger@4securemail.com

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902. Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

7-18-16

Well Log Number:

CLAC 48

Well Identification #:

L-123473