

CLAC

CLAC 500 RECEIVED 00500

RECEIVED

S/3E/27

STATE OF OREGON WATER WELL REPORT (as required by ORS 537.765)

JAN 10 1989

(START CARD) #

(1) OWNER: Name Moller's Nursery Inc, Address 34519 S.E. Lusted Road, City Gresham, State Ore, Zip 97080

(9) LOCATION OF WELL by legal description: County Clatsop, Township 1S, Range 3E, Section 27, Tax Lot 500, Lot, Block, Subdivision, Street Address of Well (or nearest address) N.A.

(2) TYPE OF WORK: [X] New Well, [] Deepen, [] Recondition, [] Abandon

(3) DRILL METHOD: [X] Rotary Air, [] Rotary Mud, [] Cable, [] Other

(4) PROPOSED USE: [] Domestic, [] Community, [] Industrial, [X] Irrigation, [] Thermal, [] Injection, [] Other

(10) STATIC WATER LEVEL: 218 ft. below land surface, Date 6-16-88, Artesian pressure lb. per square inch, Date

(5) BORE HOLE CONSTRUCTION: Special Construction approval Yes No, Depth of Completed Well 465 ft., Explosives used [X] Type Amount

(11) WATER BEARING ZONES: Table with columns From, To, Estimated Flow Rate, SWL. Data: 60-70 (20), 287-450 (400)

HOLE SEAL table: Diameter, From, To, Material, Amount. Data: 14-125 (cement, 46 sacks), 10-287, 8-465

(12) WELL LOG: Table with columns Material, From, To, SWL. Data: top soil (0-2), red clay (2-60), black rock (60-90), cemented gravel and large boulders (90-200), black rock (200-236), cemented gravel (236-287), loose gravel (287-450), yellow sand (450-460), blue clay (460-465)

How was seal placed: Method [] A [] B [X] C [] D [] E, Backfill placed from ft. to ft. Material, Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Table with columns Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Data: 10 (+2, 125, 250) [X] Steel, [] Plastic, [X] Welded, [] Threaded; 8 (+2, 465, 250) [X] Steel, [] Plastic, [X] Welded, [] Threaded

Final location of shoe(s) 125, 465

(7) PERFORATIONS/SCREENS: [X] Perforations Method airknife, [] Screens Type Material

Table for perforations: From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner. Data: 250-450, 1/4/2, 1200, [X] Casing, [] Liner

Date started 5-25-88, Completed 6-16-88

(8) WELL TESTS: Minimum testing time is 1 hour, [] Pump, [] Bailer, [X] Air, [] Flowing, Yield gal/min 400, Drawdown, Drill stem at 440, Time 4 hr.

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief. WWC Number, Date

Temperature of water, Depth Artesian Flow Found, Was a water analysis done? [] Yes By whom, Did any strata contain water not suitable for intended use? [] Too little, [] Salty [] Muddy [] Odor [] Colored [] Other, Depth of strata:

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief. WWC Number 616, Date 7-10-88

NO 3467
RECEIVED

“START CARD”
NOTICE OF BEGINNING OF WELL CONSTRUCTION
(as required by ORS 537.762)

MAY 9 1988

WATER RESOURCES DEPT
SALEM, OREGON

This form must be completed, signed by both the owner (or authorized agent) and constructor, and the original delivered to the Water Resources Department prior to commencement of construction, alteration or abandonment of each well.

Owner's Name and Mailing Address Mollers Nursery Inc
34519 S.E. Lusted Road
Gresham, OR 97080

Proposed Commencement Date 5-9-88

Proposed Well Depth 450, Diameter 10
and Use:
 Domestic Community Industrial Irrigation
 Thermal Injection Other

Proposed Well Location: County CLACK.
Township R1S (N or S) Range 4E (E or W) Section 27

- At least 2 of these must be provided
- 1. _____ 1/4 of _____ 1/4 of above section
 - 2. street address of well location _____
 - 3. tax lot number of well location 500
 - 4. attach approved map with location identified.
(see reverse of this form for approved maps)

We hereby certify that we have read the back of this form, and that to the best of our knowledge the information provided herein is accurate and the well is being properly located from septic tanks and septic drain fields.

x [Signature]
Owner's Signature
President
Title
5/6/88
Date

x [Signature]
Bonded Water Well Constructor
License No. 616
Company Ted Pulliam

Note: This is not a Water Right application. The owner is responsible for obtaining a Water Right through the Water Resources Department if required.