

STATE OF OREGON  
WATER WELL REPORT  
(as required by ORS 537.765)

Clac  
51454

FEB 28 1997

WATER RESOURCES DEPT. (START CARD) # W-94780  
SALEM, OREGON

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number 1-97  
Name Jon W. / Bobbe W. Crew  
Address 10025 SE Eastmont Drive  
City Gresham State OR Zip 97080

(2) TYPE OF WORK  
 New Well  Deepening  Alteration (repair/recondition)  Abandonment

(3) DRILL METHOD:  
 Rotary Air  Rotary Mud  Cable  Auger  
 Other

(4) PROPOSED USE:  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Livestock  Other

(5) BORE HOLE CONSTRUCTION:  
Special Construction approval  Yes  No Depth of Completed Well 511 ft.  
Explosives used  Yes  No Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE		SEAL	
Diameter	From To	Material	From To Sacks or pounds
15"	0 106	Bentonite	0 48 67 sacks
12"	106 275	Cement	
8"	275 511	w/8% Bentonite	48 275 60 sacks

How was seal placed: Method  A  B  C  D  E  
 Other

Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

(6) CASING/LINER:

Diameter	From To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 8-inch	438 250	24	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner: 6-inch	430 511	250	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) 498 feet

(7) PERFORATIONS/SCREENS:

Perforations Method Saw  
 Screens Type \_\_\_\_\_ Material \_\_\_\_\_

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
438	510	48	290			<input type="checkbox"/>	<input checked="" type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour  
 Pump  Bailer  Air  Flowing  Artesian

Yield gal/min	Drawdown	Drill stem at	Time
7.5 gpm	18 feet		1 hr.

Temperature of water 53° Depth Artesian Flow Found \_\_\_\_\_  
Was a water analysis done?  Yes By whom \_\_\_\_\_  
Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other Restricted by WRP # 8-12365  
Depth of strata: \_\_\_\_\_

(9) LOCATION OF WELL by legal description:  
County Clatsop Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
Township 1-South N or S Range 3-East E or W. WM.  
Section 25 E SW 1/4 SE 1/4  
Tax Lot 100 Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
Street Address of Well (or nearest address) Near Telford Road; at the end of S.E. Coachman Lane

(10) STATIC WATER LEVEL:  
108 ft. below land surface. Date 1/29/97  
Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

(11) WATER BEARING ZONES:  
Depth at which water was first found 4.5 feet

From	To	Estimated Flow Rate	SWL
4.5 feet	166 feet	?	33
166 feet	206 feet	?	33
352 feet	511 feet	75 plus gpm	108

(12) WELL LOG:  
Ground Elevation \_\_\_\_\_

Material	From	To	SWL
Clay; orange	0	30	
Cemented gravel, cobbles and boulders	30	166	33
Cemented gravel and cobbles	166	206	33
Clay and gravel; brown	206	238	
Clay; sticky, brown	238	282	
Clay; brown	282	318	
Clay; gray	318	352	
Clay; gravel lenses	352	495	114 *
Gravel; coarse, gray	495	511	114 *

Tagged well: 1/29/97.  
Removed rig: 1/24/97.  
Removed equipment: 1/29/97.  
\* 1/24/97

Date started 10/5/96 Completed 1/26/97  
(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Steinman Bros. WWC Number 1  
Signed Drilling Co. Date \_\_\_\_\_

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Robert McDonald WWC Number 1  
Date 2/23/97