

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310 within 30 days from the date of well completion.

CLAC

05188

STATE OF OREGON ENGINEER

(Please type or print)

RECEIVED

WELL REPORT 21 1967

State Well No.

State Permit No.

33A8c

2/3-

(1) OWNER:

Name Elmore Mostul
Address Rte 5 Box 715
Oregon City, Ore. 97045

(2) LOCATION OF WELL:

County Clackamas Driller's well number 24-67
SW 1/4 SE 1/4 Section 28 T. 2S R. 3E W.M.
Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐ Rotary ☐ Driven ☐
Irrigation ☒ Test Well ☐ Other ☐ Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(5) TYPE OF WELL:

(6) CASING INSTALLED: plus one ft. above gr. Threaded ☐ Welded ☒
....." Diam. from ft. to ft. Gage
....." Diam. from ft. to ft. Gage
....." Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used Mills Knife
Size of perforations 1/4 in. by 2 in.
.....292 perforations from62 ft. to139 ft.
..... perforations from ft. to ft.
..... perforations from ft. to ft.
..... perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal drill cuttings & clay
Depth of seal18 ft. Was a packer used? yes
Diameter of well bore to bottom of seal 12" to 18" to 10" to 34"
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 5 ft. below land surface Date 5/27/67
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom?

Yield: 125 gal./min. with 131 ft. drawdown after hrs.
" 110 " 100 " 1 "

Baller test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 54 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing

Depth drilled 158 ft. Depth of completed well 157 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Top soil	0	1
Gravel & clay conglomerate	1	15
Gravel, loose conglomerate	15	18
Gravel, cement conglomerate	18	34
Clay, conglomerate	34	35
Gravel, cement conglomerate	35	52
Gravel, loose conglomerate	52	94
Gravel & boulder, conglomerate	94	113
Gravel, loose conglomerate	113	125
Sand, coarse & brown clay conglomerate	125	153
Sand, stone	133	135
Sand, & clay brown conglomerate	135	150
Sand, fine brown	150	158

Work started 4/11/67 19 Completed 4/27/67 19
Date well drilling machine moved off of well 5/1/67 19

(13) PUMP:

Manufacturer's Name
Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Steinman Bros.
(Person, firm or corporation) (Type or print)

Address Milwaukie, Oreg.

Drilling Machine Operator's License No. 69

[Signed] Steinman Bros.
(Water Well Contractor)

Contractor's License No. 1 Date 4/6/67, 19.....