

Clac
52000

JUL 10 1997

(1) OWNER: Well No. L07378
Name SCENIC FRUIT COMPANY
Address 7510 SE ALTMAN ROAD
City GRESHAM St OR Zip 97080

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMEST/IRRIGAT

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO Depth of Compl. Well 1100 ft
Explosives used NO Type Amount

HOLE			SEAL			
Diam.	From	To	Material	From	To	Amount
14	0	50	BENTONITE	0	50	69 SACKS
9 5/8	50	360	CEMENT	300	360	50 SACKS
7 1/2	360	1000	CEMENT	540	580	40 SACKS
6	1000	1100				

Seal placement method

Backfill: from ___ ft to ___ ft Material
Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

	Diam.	From	To	Gauge	Material	Connection
Casing	8	+1	360	.250	STEEL	WELDED
	6	+2	580	.250	STEEL	WELDED

Liner

Final Location of shoe(s) 360'-7 1/2" TUBEX; 580'-6"

(7) PERFORATIONS/SCREENS:

[] Perf. Method
[] Screens Type Material

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner

(8) WELL TESTS: Minimum testing time is 1 hour

Test type PUMP

Yield GPM	Draw-down	Drill stem at	Time
200	180		1 hr.
200	180		12 HR

Temperature of water 52F Depth Artesian Flow Found
Was water analysis done? NO By whom
Reason for water not suitable for use
Depth of strata

(9) LOCATION OF WELL by legal description:

County CLACK Lat. ° ' " Long. ° ' "
Township 2 S Range 5 E WM.
Section 30 NE 1/4 SE 1/4
Tax Lot 01600 Lot Block Subdivision
Street Address of Well (or nearest Address)
FIRWOOD ROAD SANDY, OR 97055

(10) STATIC WATER LEVEL:

360 ft. below land surface. Date 06/10/97
Artesian pressure lb per square in. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 20		Est Flow Rate	SWL
From	To		
20	30	10-20 GPM	12
200	280	150 GPM	132
960	1100	200+ GPM	360

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
TOP SOIL	0	2	
RED CLAY	2	20	
RED CLAY & GRAVEL	20	30	12
MEDIUM ROCK	30	43	
CEMENTED GRAVEL & BOULDERS	43	280	132
BLUE CLAY	280	540	
MULTI-COLORED MEDIUM ROCK	540	960	
BROKEN MULTI-COLORED ROCK RHODENDRON FORMATION	960	1100	360

WELL #2 OF PERMIT FOR 6 WELLS.

Date started 05/13/97

Completed 06/10/97

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed WWC Number
Date

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed WWC Number 616
Date 07/08/97