

RECEIVED

SEP 29 1997

WELL I.D.#

L16816

STATE OF OREGON WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

WATER RESOURCES DEPT.

(START CARD) #

92349

Instructions for completing this report are on the back of this form.

(1) OWNER:

Well Number

Name Glenn Fincher

Address 30163 S. Needy Rd

City Canby State Or Zip 97013

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger

☐ Other

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation

☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☐ No Depth of Completed Well 292 ft.

Explosives used ☐ Yes ☐ No Type Amount

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
10	1	50	Bentonite	1	50	26 sacks
6	50	292				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other Granular Bentonite method

Backfill placed from 230 ft. to 292 ft. Material pea

Gravel placed from 230 ft. to 292 ft. Size of gravel pea

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
6	0	222	.25	☒	☐	☐	☐
Casing:				☐	☐	☐	☐
4	3	292	1160	☐	☐	☐	☐
Liner:				☐	☐	☐	☐

Final location of shoe(s) 222

(7) PERFORATIONS/SCREENS

From	To	Slot	Number	Diameter	Material	Casing	Liner
277	287	.010	4	4		☐	☐
119	149	1/8	70	4		☐	☐
<u>UPPER PERFORATIONS TO HELP WATER FLOW TO PUMP ONLY</u>							

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Flowing Artesian Time
50	15		3 hr 1 hr.

Temperature of water 53 Depth Artesian Flow Found

Was a water analysis done? ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County CLACKAMAS Latitude Longitude

Township 5s N or S Range 1e E or W. WM.

Section 4 NW 1/4 Nw 1/4

Tax Lot 400 Lot Block Subdivision

Street Address of Well (or nearest address)

Needy and Bernards Roads, SE corner

(10) STATIC WATER LEVEL:

44 ft. below land surface.

Date 30 Aug

Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 34

From	To	Estimated Flow Rate	SWL
34	292		44

(12) WELL LOG:

Ground Elevation

Material	From	To	SWL
Soil	1	3	
Clay, brown, sandy	3	34	
Cemented gravel, brown	34	54	
Sand, Brown, fine	54	65	
Sand & Gravel, brown	65	69	
Clay, grey	69	71	
Clay, grey & Black sand	71	73	
Silt, grey w/ black sand	73	89	
Sand, black	89	95	
Sand & Gravel, black	95	116	
Cemented gravel, grey	116	138	
Clay, grey	138	184	
Sand Greenish black	184	187	
Clay, blue	187	205	
Clay, grey	205	212	
Sand, grey, cemented	212	217	
Clay, grey	217	249	
Sand, fine, magenta	249	257	
Clay, grey	257	285	
Sand, black	285	290	
Clay, grey	290	292	

Date started JULY 21 Completed AUG 30, 1997

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number

Signed

Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 743

Signed Richard Beck

Date SEP 19, 1997