

STATE OF OREGON
WATER WELL REPORT

(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

(1) OWNER:

Well Number

Name BEN J. Franklin - Ben Franklin Nursery
Address 35674 SE Squawmnt Rd
City Estacada State OR Zip 97023

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☒ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☒ Yes ☐ No Depth of Completed Well 265 ft.
Explosives used ☐ Yes ☐ No Type Amount

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
10"	0	85	Cement	0	85	34 sacks
6"	85	265				

How was seal placed: Method ☐ A ☒ B ☒ C ☐ D ☐ E
☐ Other

Backfill placed from ft. to ft. Material
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+2	85	250	☒	☐	☒	☐
Liner: 5"	65	265	160	☐	☒	☐	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

From		To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
85	265	1/8 x 8	187	5	20		☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump	☐ Bailer	☐ Air	Flowing
Yield gal/min	Drawdown	Drill stem at	Artesian
72	42'		8 hrs + hr.

Temperature of water 56 Depth Artesian Flow Found
Was a water analysis done? ☐ Yes By whom
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other
Depth of strata:

(9) LOCATION OF WELL by legal description:

County Clackamas Latitude Longitude
Township 3 N or S Range 4 E or W. WM.
Section 27 NW 1/4 SE 1/4
Tax Lot 2700 Lot Block Subdivision
Street Address of Well (or nearest address) 35674 SE Squawmnt Rd Estacada OR 97023

(10) STATIC WATER LEVEL:

12 ft. below land surface. Date 3-24-98
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 230

From	To	Estimated Flow Rate	SWL
32	64	Sealed OFF	5'
230	255	72+	12

(12) WELL LOG:

Ground Elevation

Material	From	To	SWL
TOP SOIL	0	2	
Clay Brown	2	32	
Boulders & Gravel	32	64	
Clay Brown	64	67	
Red sandstone Rock - Lava	67	230	
Lava Rock - Red	230	255	12'
Lava Rock Black	255	265	

Date started 3-13-98 Completed 3-24-98

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed Thomas Youngberg WWC Number 1512
Date 3-13-98 Date 5-10-98

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed W.O. Gammberg WWC Number 257
Date 5-10-98